


GENERAL CONDUIT & DUCT BANK NOTES

- MINIMUM CONDUIT SIZE SHALL BE 3/4" IN DIAMETER. LARGER SIZES SHALL BE INSTALLED WHERE NOTED OR WHERE REQUIRED BY NEC.
- ALL EXTERIOR AND INTERIOR EXPOSED ABOVE GRADE COUDUIT SHALL BE RIGID GALVANIZED STEEL EXCEPT WHERE NOTED OTHERWISE ON DRAWINGS.
- 3. WHERE METAL CONDUIT IS IN DIRECT CONTACT WITH EARTH OR CONCRETE IT SHALL RECEIVE ONE COAT, 8 DRY-MILS, COAL TAR EPOXY, OR EQUAL. INCLUDE ANY PRIMER COATS AS MAY BE REQUIRED. APPLY COATINGS IN CONFORMANCE WITH MFR'S DIRECTIONS AND RECOMMENDATIONS. AT THE CONTRACTOR'S OPTION, PVC COATED GALVANIZED RIGID STEEL CONDUIT MAY BE USED IN LIEU OF TAR COATING BELOW GRADE
- 4. CONCRETE ENCASED SCHEDULE 40 PVC DUCT BANK SHALL BE INSTALLED FOR ALL BELOW GRADE DUCT BANK, EXCEPT WHERE NOTED ABOVE AND IN THE SPECIFICATIONS. WHERE APPLICABLE, ALL BELOW GRADE CONDUIT UNDER PAVED SURFACES RECEIVING VEHICULAR TRAFFIC SHALL BE REINFORCED. TRANSITION FROM BELOW GRADE SCHEDULE 40 PVC CONDUIT TO RIGID METAL CONDUIT SHALL BE WITHIN CONCRETE ENCASEMENT AS DETAILED
- CONDUIT RUNS EMBEDDED IN STRUCTURE WALLS OR FLOORS MAY BE SCHEDULE 40 PVC OR PVC COATED GALVANIZED RIGID STEEL, EXCEPT WHERE NOTED ON THE DRAWINGS, SPECIFIED OR DIRECTED BY THE OWNERS AUTHORIZED REPRESENTATIVE.
- 6. CONDUIT SIZE AND FILL REQUIREMENTS SHALL COMPLY WITH CHAPTER 9, AND ANNEX C OF
- 7. LIQUID-TIGHT FLEXIBLE METAL CONDUIT SHALL BE PROVIDED AS A CONNECTION BETWEEN EACH MOTOR JUNCTION BOX (OR ANY OTHER PIECE OF EQUIPMENT SUBJECT TO MOVEMENT OR VIBRATION) AND BALANCE OF CONDUIT SYSTEM. LIQUID-TIGHT FLEXIBLE METAL CONDUIT SHALL NOT EXCEED 3' IN LENGTH AND SHALL BE OZ-GEDNEY TYPE UAG, OR EQUIVALENT. IN HAZARDOUS (CLASSIFIED) LOCATIONS FLEXIBLE METAL CONDUIT SHALL BE CONSTRUCTED WITH STAINLESS-STEEL BRAIDED EXTERIOR SURFACE.
- 8. ALL MOUNTING HARDWARE AND FASTENERS FOR CONDUITS AND EQUIPMENT SHALL BE
- IN ORDER TO MAINTAIN NEC RATINGS AND CLASSIFICATIONS OF CABLES, DO NOT COMBINE CONDUIT CONTENTS OR MODIFY CONDUIT MATERIALS OF CONSTRUCTION UNLESS SPECIFICALLY DIRECTED OR SHOWN OTHERWISE



LAWS, ORDINANCES AND REQUIREMENTS IN FORCE, ANY INSTALLATIONS WHICH VOID THE U.L. LISTINGS (OR THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRENTY OF A DEVICE SHALL NOT BE PREMITTED.

REVISIONS

GEND

VIA

NDARD ABBRE

STAI

AB

JRO

DLP

02/29/08

07258-06

ILLINOIS PROJECT: RFD-3787 A.I.P. PROJECT: 3-17-0088-XX FINAL SUBMITTAL SHEET 37 OF 83 SHEETS