

FILE NAME = S:\JUL15\2013-6399\6346\BDS\Materials\6000 Sheets\ENR3-14-500.dgn

				CONSTRUCTION CODE								
				80% FED 20% STATE	100% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% JOLIET	100% JOLIET	100% JOLIET	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY 0004	ROADWAY 0004	RAMP B	RAMP D	VOYAGER LN.	RAMP B	RAMP D	INTER- CONNECT 0021	STREET LIGHTING 0021
				TRAFFIC SIGNALS 0021					EVP 0021			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,669	2,669								
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	11,321	11,321								
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	2,869	2,869								
42001300	PROTECTIVE COAT	SQ YD	4,195	4,195								
44000100	PAVEMENT REMOVAL	SQ YD	372	372								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	612	612								
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,016	1,016								
44213200	SAW CUTS	FOOT	567	567								
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SQ YD	1,227	1,227								
50105220	PIPE CULVERT REMOVAL	FOOT	6	6								
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1								
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1								
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	27	27								
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	42	42								
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	30	30								
* SPECIALTY ITEM												



1170 SOUTH HOUSLIT ROAD
JOLIET, ILLINOIS 60431
STRAND ASSOCIATES
(815) 744-4200

USER NAME = B11P

MODEL NAME = Default

PLOT SCALE = 2.0000" = 1'

PLOT DATE = 12/23/2013

DESIGNED = JLB

DRAWN = DJW

CHECKED = BMA

DATE = 12/17/13

REVISED =

REVISED =

REVISED =

REVISED =

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SCALE: SHEET OF SHEETS STA. TO STA.

F.A.
RTED
S75

SECTION
14-N

COUNTY
WILL

TOTAL
SHEETS
163

SHEET
NO.
6

CONTRACT NO. 60W13

ILLINOIS FED. AID PROJECT