

CODE PAY ITEMS		20200600	21400100	25000200	25000400	25000500	25000600	25100115	28000250
LOCATION	LENGTH (FEET)	EXC. & GRADING EXIST. SHOULDER (UNIT)	GRADING & SHAPING DITCHES (FOOT)	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTRIENT (POUND)	PHOSPHORUS FERT. NUTRIENT (POUND)	POTASSIUM FERT. NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)	TEMP. EROSION CONTROL SEEDING (POUND)
RIGHT SIDE									
STA. 30+81.00 TO STA. 103+22.02	7,241.02	72.41	7,241.02	1.00	89.76	89.76	89.76	1.00	99.74
STA. 103+22.02 TO STA. 106+58.77	336.75	3.37	336.75	0.05	4.17	4.17	4.17	0.05	4.64
STA. 106+58.77 TO STA. 117+09.00	1,050.23	10.50	1,050.23	0.14	13.02	13.02	13.02	0.14	14.47
STA. 117+82.00 TO STA. 133+45.48	1,563.48	15.63	1,563.48	0.22	19.38	19.38	19.38	0.22	21.54
STA. 133+45.48 TO STA. 136+87.66	342.18	3.42	342.18	0.05	4.24	4.24	4.24	0.05	4.71
STA. 136+87.66 TO STA. 170+06.63	3,318.97	33.19	3,318.97	0.46	41.14	41.14	41.14	0.46	45.72
STA. 170+06.63 TO STA. 174+93.38	486.75	4.87	486.75	0.07	6.03	6.03	6.03	0.07	6.70
STA. 174+93.38 TO STA. 193+79.00	1,885.62	18.86	1,885.62	0.26	23.38	23.38	23.38	0.26	25.97
SUB-TOTAL	16,225	162.25	16,225	2.23	201.14	201.14	201.14	2.23	223.48
LEFT SIDE									
STA. 30+82.00 TO STA. 61+19.00	3,037.00	30.37	3,037.00	0.42	37.65	37.65	37.65	0.42	41.83
STA. 61+93.00 TO STA. 103+22.02	4,129.02	41.29	4,129.02	0.57	51.19	51.19	51.19	0.57	56.87
STA. 103+22.02 TO STA. 106+58.77	336.75	3.37	336.75	0.05	4.17	4.17	4.17	0.05	4.64
STA. 106+58.77 TO STA. 110+30.00	371.23	3.71	371.23	0.05	4.60	4.60	4.60	0.05	5.11
STA. 111+87.00 TO STA. 117+05.00	518.00	5.18	518.00	0.07	6.42	6.42	6.42	0.07	7.13
STA. 117+67.00 TO STA. 133+45.48	1,578.48	15.78	1,578.48	0.22	19.57	19.57	19.57	0.22	21.74
STA. 133+45.48 TO STA. 136+87.66	342.18	3.42	342.18	0.05	4.24	4.24	4.24	0.05	4.71
STA. 136+87.66 TO STA. 171+31.63	3,443.15	34.43	3,443.15	0.47	42.68	42.68	42.68	0.47	47.43
STA. 171+31.63 TO STA. 175+80.88	449.25	4.49	449.25	0.06	5.57	5.57	5.57	0.06	6.19
STA. 175+80.88 TO STA. 192+17.00	1,636.12	16.36	1,636.12	0.23	20.28	20.28	20.28	0.23	22.54
SUB-TOTAL	15,841.18	158.41	15,841.18	2.18	196.38	196.38	196.38	2.18	218.20
TOTAL	32,066	320.66	32,066	4.41	397.52	397.52	397.52	4.41	441.68
APP. RATE OR CONV. FACTOR		100 FT = 1 UNIT		1 ACRE=43,560 SQFT	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE		100 LBS/ACRE

CODE PAY ITEMS	70100460
LOCATION	TRAFFIC CONTROL AND PROTECTION, STD. 701306 (L SUM)
STA. 30+81.00 TO STA. 193+17.00	1
TOTAL	1

CODE PAY ITEMS	70100500
LOCATION	TRAFFIC CONTROL AND PROTECTION, STD. 701326 (L SUM)
STA. 30+81.00 TO STA. 193+17.00	1
TOTAL	1

CODE PAY ITEMS	70103815
LOCATION	TRAFFIC CONTROL SURVEILLANCE (CAL DA)
STA. 30+81.00 TO STA. 193+17.00	15
TOTAL	15