



**NOTES:**

- ALL SIGNS IN CONFLICT WITH THIS STAGE OF CONSTRUCTION SHALL BE COVERED.
- ALL STRIPING AND RRPM IN CONFLICT WITH THIS STAGE OF CONSTRUCTION SHALL BE REMOVED.
- PLACING, MAINTAINING AND REMOVING TEMPORARY PAVEMENT MARKINGS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST FOR TRAFFIC CONTROL AND PROTECTION STANDARD 701321.
- ALL TEMPORARY BRIDGE TRAFFIC SIGNALS FOR STAGE I & II WILL BE MEASURED AS ONE UNIT.
- THE BASE COURSE (OPTION) IN CONFLICT WITH THE CONSTRUCTION OF THE PROPOSED BRIDGE DURING STAGE II SHALL BE REMOVED AND PAID FOR AS SHOULDER REMOVAL.

**SYMBOLS:**

WORK AREA	DETECTOR LOOP
TRAFFIC SIGNAL	SIGN
TEMPORARY CONCRETE BARRIER	TYPE III BARRICADE
DRUM WITH STEADY BURNING LIGHT	TYPE C BIDIRECTIONAL REFLECTOR

FILE NAME =	USER NAME = detersbj	DESIGNED - JD	REVISED - BJH 01/13/2014
#FILE#		DRAWN - JD	REVISED -
	PLOT SCALE = 48.0000' / in.	CHECKED - SD	REVISED -
	PLOT DATE = 1/13/2014	DATE - 10/18/13	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STAGE 2 PLAN**

SCALE: 1" = 20'    SHEET NO. 5 OF 5 SHEETS    STA. 741+50.00 TO STA. 747+00.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
711	116BR-1	VERMILION	84	28
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70614	

**EFK Moen, LLC**  
Civil Engineering Design