* CMAQ FUNDING (COLUMNS 1, 28, 29)

\+ NHPP FUNDING (COLUMNS 2, 4, 6 -11, 13-15, 17-18, 20)

SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																												
					ROADWAY	TRAFFIC SIGNALS																		EVP							INTER-CONNECT	DMS
					0021	0021																		0021							0021	0044
					URBAN	URBAN																		URBAN							URBAN	URBAN
					*1	+2	3	+4	5	+6	+7	+8	+9	+10	+11	12	+13	+14	+15	16	+17	+18	19	+20	21	22	23	24	25	26	27	*28	*29
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	216					4	36	4	8	60	4	4	12	8	8	12	8	24	4		20									
	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	148							10	10				20		10	30	13.5	27			27									
	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	195						13	13.5	14	64			22			16		13			39									
	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	836						92	46	50	242	46	42	42		100	92	42	42												
	87900200	DRILL EXISTING HANDHOLE	EACH	266		1				38	9	5	72	12	4	12	3	22	20	6	9	7		12								34	
	87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	1																				1									
	87703282	STEEL MAST ARM ASSEMBLY & POLE WITH DUAL MAST ARMS, 75 FT. & 42 FT.	EACH	1						1																							
	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	233						17	12	14	62	10	12	12		28	24	12	16			14									
	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	73					4	2	2	4	21	6	2	2	1	6	4	5	4			10									
	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	53						10	2	1	12	4	2	2	1	3	4	2	4			6									
	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	73						5	6	3	5	6	6	6	1	11	12	2	4			6									
	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	130						9			41	5	2		2	12	16	8	18	1		16									
	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	300						14	18	17	69	16	18	18	1	39	36	14	20			20									
	88200510	TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	8						8																							
	88500100	INDUCTIVE LOOP DETECTOR	EACH	91		2		3	2	12			27	5	4	6	5		5	5	8	2		5									

1

MODEL: Default
FILE NAME: pw:\\kh-pw.bentley.com:kh-pw-01\Documents\01 Active Projects\MW-CHS-168959100 - IL 64\Phase II\2 Design\CAD\Plan Sheets\West Corridor General Sheets\D108121-sht-SQQ-01 KHA.dgn

Kimley»Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
4201 WINFIELD ROAD, SUITE 600
WARRENVILLE, IL 60555
PHONE: 630-487-5550
WWW.KIMLEY-HORN.COM

USER NAME =	DESIGNED - AMK	REVISED -	
	DRAWN - JJT	REVISED -	
PLOT SCALE =	CHECKED - SRS	REVISED -	
PLOT DATE =	DATE - 3/21/2025	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 9 OF 14 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	2020-263-SUR,SW&TS	DUPAGE	529	22
		CONTRACT NO. 62N33		
		ILLINOIS	FED. AID PROJECT	

REV-SEP