

SUMMARY OF QUANTITIES				CONSTRUCTION CODE - 100% STATE / 0005							
				PEORIA COUNTY				STARK COUNTY			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ALTA	KICKAPOO CREEK	PARKS SCHOOL ROAD	COUNTY LINE ROAD	PRINCEVILLE	WYOMING DEPOT	TOULON	WYOMING (WEST)
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	92	59	5	14	5			9	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.0	1.30	0.10	0.30	0.10			0.20	
* 25100115	MULCH, METHOD 2	ACRE	1.00	0.65	0.05	0.15	0.05			0.10	
25100630	EROSION CONTROL BLANKET	SQ YD	269			269					
28000305	TEMPORARY DITCH CHECKS	FOOT	80	56		24					
28000400	PERIMETER EROSION BARRIER	FOOT	2,868	1,805		544	157			362	
28000500	INLET AND PIPE PROTECTION	EACH	8	4	2	2					
28100105	STONE RIPRAP, CLASS A3	SQ YD	23	23							
35100100	AGGREGATE BASE COURSE, TYPE A	TON	2,727	1,937	89	418	90			193	
35800100	PREPARATION OF BASE	SQ YD	5,888	3,149	400	695	389			1,255	
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	9			2	5	2			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,930	2,272	248	519	221			670	
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	3,789		495	1,557	441			1,296	
40300500	COVER COAT AGGREGATE	TON	44		5	21	5			13	

\*SPECIALTY ITEM