

SUMMARY OF QUANTITIES			UNIT	URBAN 90% FED. 10% STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION	0003			0010	0021	0031	0040	
		RDWY			BRIDGE	SIGNALS LIGHTING	LNDSCP	RET. WALL	
	ADVANCED TRANSPORTATION								
X0370050	CONTROLLER, TRAFFIC, 16 LOAD BAY, "P" CABINET (CDOT)	EACH	4			4			
X0370010	COAXIAL JUMPER CABLE (CDOT)	EACH	4			4			
X0370013	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER (CDOT)	EACH	4			4			
X0370014	CONCRETE FOUNDATION, 20" DIAMETER, 3/4" ANCHOR RODS, 13" BOLT CIRCLE (CDOT)	EACH	10			10			
X0370068	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	29			29			
X0370015	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE (CDOT)	EACH	10			10			
X0370016	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/4" ANCHOR RODS, 17 1/4" BOLT CIRCLE (CDOT)	EACH	2			2			
X0370051	CUT OFF POLE AND INSTALL CAP (CDOT)	EACH	1			1			
X0370018	ELECTRIC CABLE IN CONDUIT NO. 14 19/C (CDOT)	FOOT	5320			5320			
X0370052	ELECTRIC CABLE IN CONDUIT NO. 4 2/C (CDOT)	FOOT	577			577			
X0370053	ELECTRIC CABLE NO. 14 3/C, SHIELDED (CDOT)	FOOT	2768			2768			
X0370021	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID (CDOT)	EACH	4			4			

• SPECIALTY ITEM

 PATRICK ENGINEERING INC 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = kwoopen@dyg-lisle1	DESIGNED - CPK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT CONFIG = PDFIgray_small.plt	DRAWN - MJP	REVISED -						2746	1616B	COOK	404	36
	PLOT SCALE = 1:100	CHECKED - JAH	REVISED -						60J14				
	PLOT DATE = 2/18/2013 4:48:05 PM	DATE = 2/18/2013	REVISED -										
0:\100T\21050-086-CumberlandAve\Drawings\CADD Sheets\0160J14-500_01.dgn				SCALE: NA	SHEET	500-33 OF 36	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

Q:\100T\21850.005\CumberlandAve\Drawings\CA000 Sheets\0160J14-500.01.dgn

Rev. 4-11-13