FINAL SURVEY	NOTE BOOK	SURVEYED	PLOTTED	TEMPLATE	AREAS	AREAS CHECKED
NO.		BY				
		DATE				

ORIGINAL SURVEY	NOTE BOOK	SURVEYED	PLOTTED	TEMPLATE	AREAS	AREAS CHECKED
NO.		BY				
		DATE				

URS
100 S.WACKER DR.
SUITE 1500
CHICAGO IL.60606
TEL (312)939-1000
FAX (312)939-4198

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

715 710 705 700 695 690

STAGE A TEMP

PRE-STAGE TEMP

℄ 135TH STREET

EX ROW

ESMT.

1:3

-2.00 %

STAGE A TEMP EARTH EXCAVATION 0.5 SQ FT
UNSUITABLE 6.0 SQ FT
EMBANKMENT 6.0 SQ FT

PRE-STAGE EARTH EXCAVATION 1.4 SQ FT
UNSUITABLE 11.6 SQ FT
EMBANKMENT 24.2 SQ FT

0
EX 8" SANS

EX GAS

651+50.00

STAGE A TEMP

PRE-STAGE TEMP

℄ 135TH STREET

PR ROW

EX ROW

ESMT.

1:3

-2.50 %

-2.00 %

STAGE A TEMP EARTH EXCAVATION 0 SQ FT
UNSUITABLE 4.2 SQ FT
EMBANKMENT 4.7 SQ FT

PRE-STAGE EARTH EXCAVATION 2.0 SQ FT
UNSUITABLE 10.7 SQ FT
EMBANKMENT 16.8 SQ FT

0
EX 8" SANS

EX GAS

651+00.00

FILE NAME = D160M62-SHT-XSSHT12.dgn	USER NAME = Anthony.Plutz	DESIGNED - TRK	REVISED -
		DRAWN - TRK	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - MJT	REVISED -
	PLOT DATE = 3/13/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

135TH STREET TEMPORARY PAVEMENT CROSS SECTIONS

SCALE:1"=10'H;1"=5'V | SHEET NO. 1 OF 13 SHEETS | STA. 651+00.00 TO STA. 651+50.00

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-5	COOK	778	601
	XS-T135-01	CONTRACT NO. 60M62		
	ILLINOIS FED. AID PROJECT			