

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				0014	100% STATE
67100100	MOBILIZATION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	21	21	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	17,279	17,279	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5,987	5,987	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5,820	5,820	
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2	2	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,250	19,250	
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	2,282	2,282	
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	461	461	
* 78008210	POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	1,942	1,942	
* 78008220	POLYUREA PAVEMENT MARKING, TYPE I - LINE 5"	FOOT	243	243	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16	

SPECIALTY ITEM \*

FILE NAME: D:\6862\shc\500.dgn  
 USER NAME: J00T  
 PLOT SCALE: 1/8" = 100.0000' / IN.  
 PLOT DATE: 1/18/2013

**CR & A**  
 CHRISTIAN-ROGE & ASSOCIATES, INC.  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-8274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - JANUARY 17, 2013	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 I-55

SCALE: NONE SHEET NO. 4 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	87B, D-BR-1	WILL	106	6
CONTRACT NO. 60R62			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	