

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	0014	
				100% STATE	
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	100	100	
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	52,361	52,361	
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SO YD	64	64	
Z0001905	STRUCTURAL STEEL REPAIR	POUND	8830	8830	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	7,296	7,296	
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SO YD	3,508	3,508	
* Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	
Z0012102	CONCRETE BRIDGE DECK SCARIFICATION (3/8 INCH)	SO YD	3,508	3,508	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	2,427	2,427	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0015802	PLUG EXISTING DECK DRAINS	EACH	80	80	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	30	30	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	40	40	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	832	832	

SPECIALTY ITEM *

FILE NAME: *D16062-sh1-500.dgn
 USER NAME: *J001
 PLOT SCALE: 100.0000 "/>



CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.
 DRAWN - A.C.S.
 CHECKED - M.P.
 DATE - JANUARY 17, 2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-55

SCALE: NONE SHEET NO. 6 OF 7 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	87B, D-BR-1	WILL	106	8
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R62	

Rev.