

SUMMARY OF QUANTITIES

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%	
					COUNTY = 20%	
					TRAINEES	OTHER
					0042	0044
Δ	20200100	EARTH EXCAVATION	CU YD	6412		6412
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	650		650
	20400800	FURNISHED EXCAVATION	CU YD	795		795
	20800150	TRENCH BACKFILL	CU YD	64		64
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1950		1950
	21101515	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12695		12695
	21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100		100
	25000210	SEEDING, CLASS 2A	ACRE	1.8		1.8
	25000310	SEEDING, CLASS 4	ACRE	0.7		0.7
	25000314	SEEDING, CLASS 4B	ACRE	0.25		0.25
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	162		162
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	162		162
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	162		162
	25100115	MULCH, METHOD 2	ACRE	1.8		1.8
	25100630	EROSION CONTROL BLANKET	SQ YD	4050		4050
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	520		520
	28000305	TEMPORARY DITCH CHECKS	FOOT	30		30
	28000400	PERIMETER EROSION BARRIER	FOOT	545		545
	28000500	INLET AND PIPE PROTECTION	EACH	6		6
	28000510	INLET FILTERS	EACH	6		6
	28100105	STONE RIPRAP, CLASS A3	SQ YD	390		390
	28200200	FILTER FABRIC	SQ YD	390		390
Δ	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	650		650
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	5256		5256
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4771		4771
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	945		945
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	760		760
	42001300	PROTECTIVE COAT	SQ YD	450		450
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	90		90
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	5		5
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3		3
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1		1
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	206		206

Δ SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%	
					COUNTY = 20%	
					TRAINEES	OTHER
					0042	0044
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	183		183
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	92		92
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	80		80
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1		1
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	5		5
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2		2
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1		1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2485		2485
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	90		90
	67100100	MOBILIZATION	L SUM	1		1
Δ	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1
Δ	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
	72000100	SIGN PANEL - TYPE 1	SQ FT	45		45
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	119		119
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	60		60
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3100		3100
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	26		26
Δ *	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1
Δ *	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	60		60
*	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	2		2
*	81603047	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1934		1934
*	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	62		62
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	176		176
Δ *	X8250500	LIGHTING UNIT COMPLETE, SPECIAL	EACH	20		20
Δ *	X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1		1
Δ	X005472	DRAINAGE STRUCTURE SPECIAL	EACH	1		1
Δ	Z0003855	BICYCLE RACKS	EACH	1		1
Δ	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	240		240
Δ	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Δ	Z0076600	TRAINEES	HOOR	500	500	
Δ	Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOOR	500	500	

Printed: 2/28/2013 9:02:50 AM By: twd/ah

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
89 Wheeler Road
Bloomington, Illinois 61804
618-699-8700 / www.eeinc.com

**MCHENRY COUNTY DIVISION
OF TRANSPORTATION**
16111 NELSON ROAD
WOODSTOCK, IL 60098

DESIGNED - TVW	REVISED - TVW 1/21/13
DRAWN - KKP	REVISED -
CHECKED - JRL	REVISED -
DATE - 6/1/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**VIRGINIA ROAD AT ILLINOIS 31 PARK AND RIDE
SUMMARY OF QUANTITIES**

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A. RTE. N/A	SECTION 09-00370-00-PK C-91-072-10	COUNTY MCHENRY	TOTAL SHEETS 17	SHEET NO. 3
ILLINOIS FED. AID PROJECT CUM-9003(484)			CONTRACT NO. 63733	

COPYRIGHT 2011 ENGINEERING ENTERPRISES, INC.

Path: I:\ADMIN\BNA\BNA\BNA\SHEET\PROJECT\MCHENRY\09-00370-00-PK\10-072-10\10-072-10.dgn Print Key: MCHENRY-09-00370-00-PK-10-072-10