STATION		EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET FILTERS	STONE RIPRAP, CLASS A4	SEEDING, CLASS 2A	SEEDING, CLASS 4 (MODIFIED)	SEEDING, CLASS 5 (MODIFIED)	SEEDING, CLASS 4B (MODIFIED)	SEEDING, CLASS 5B	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
		25100630	28000250	28000305	28000400	28000510	28100107	25000210	X2501800	X2501820	X2502024	25000324	25000400	25000600
		(SQ YD)	(POUND)	(FOOT)	(FOOT)	(EACH)	(SQ YD)	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(POUND)	(POUND)
KREUTZER RD	10+57.50 TO 26+00	16029	331	14	3140	31	87	0.42	2.88	2.88	1.11	1.11	265	265
	26+00 TO 38+50	4214	87	70	1673	18	8	0.42	0.45	0.45	0	0	52	52
	38+50 TO 51+43.69	2702	56	0	1824	19	0	0.45	0.11	0.11	0	0	34	34
IL ROUTE 47	110+98.50 TO 120+00	1405	29	84	107	11	0	0.05	0.24	0.24	0	0	17	17
	120+00 TO 123+50	0	0	0	0	2	0	0	0	0	0	0	0	0
	123+50 TO 125+70.60	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTALS	24350	503	168	6744	81	95	1.34	3.68	3.68	1.11	1.11	368	368
	ADJUSTED QUANTITY							1.50	3.75	3.75	1.25	1.25		

STATION TO STATION		TOTALS BY STATION						
		CUT	TOPSOIL EXCAVATION+	TOPSOIL PLACEMENT	UNDERCUT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EMBANKMENT++
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
KREUTZER RD	10+57.50 TO 17+75	2511.1	1959.1	737.1	---	1222.0	552	7012.5
	17+75 TO 26+00	3240.0	2244.8	797.2	659.2	2106.8	336	15066.8
	26+00 TO 38+50	4129.8	2312.4	706.8	766.4	2372.0	1051	2954.2
	38+50 TO 47+00	3622.1	1823.1	356.7	---	1466.4	1799	1799.8
	47+00 TO 51+43.69	491.7	275.7	95.9	---	179.8	216	162.9
IL ROUTE 47	110+98.50 TO 120+00	1181.2	778.2	235.8	---	542.4	403	1082.6
	120+00 TO 125+70.60	1084.2	77.2	---	---	77.2	1007.0	47.5
AREA DB-1		6130.0	1087.4	499.8	---	587.6	5042.6	---
AREA CB-1		29700.0	4157.4	1905.1	---	2252.3	25542.6	---
CUMULATIVE TOTALS		52090.1	14715.3	5334.4	1425.6	10806.5	35949.2	28126.3

+12" DEPTH, TYPICAL

++INCLUDES 1.15 SHRINKAGE FACTOR

KREUTZER RD	13994.7	8615.1	2693.7	1425.6	7347.0	3954	26996.2
IL ROUTE 47	2265.4	855.4	235.8	0.0	619.6	1410	1130.1
AREA DB-1	6130.0	1087.4	499.8	0.0	587.6	5042.6	0.0
AREA CB-1	29700.0	4157.4	1905.1	0.0	2252.3	25542.6	0.0