

DATE	
BY	
SUPERVISOR	
NOTE BOOK	
TEMPLATE	
AREAS	
AREAS CHECKED	

DATE	
BY	
SUPERVISOR	
NOTE BOOK	
TEMPLATE	
AREAS	
AREAS CHECKED	

6	SCHEDULE OF EARTHWORK QUANTITIES (BREAKDOWN)												
STATION	DISTANCE	EARTH EXCAVATION (CUT)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION
(XX+XX)	(FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	(CU FT)	(CU FT)	(CU FT)	(CU FT)
41+28		74	26	0	4								
	22					76	24	0	4	1,661	517	0	77
41+50		77	21	0	3								
	25					98	19	0	3	2,450	463	0	75
41+75		119	16	0	3								
	25					108	28	0	13	2,700	700	0	313
42+00		97	40	0	22								
	50					89	40	0	21	4,450	1,975	0	1,050
42+50		81	39	0	20								
	36					129	40	0	15	4,626	1,440	0	540
42+86		176	41	0	10								
	14					146	21	0	5	2,037	287	0	70
43+00		115	0	0	0								
	50					72	17	0	3	3,575	825	0	125
43+50		28	33	0	5								
	22					33	23	0	5	726	506	0	110
43+72		38	13	0	5								
	13					43	9	0	5	553	111	0	65
43+85		47	4	0	5								
	15					49	6	0	5	735	83	0	68
44+00		51	7	0	4								
	10					54	8	0	4	540	80	0	40
44+10		57	9	0	4								
	30					62	14	0	4	1,845	420	0	105
44+40		66	19	0	3								
	10					73	15	0	4	725	145	0	40
44+50		79	10	0	5								
	4					81	10	0	5	324	38	0	20
44+54		83	9	0	5								
	21					72	19	0	8	1,502	389	0	168
44+75		60	28	0	11								
	25					63	28	0	15	1,575	700	0	375
45+00		66	28	0	19								
	21					65	23	0	17	1,355	473	0	357
45+21		63	17	0	15								
	29					72	26	0	22	2,074	754	0	638
45+50		80	35	0	29								
	38					134	18	0	15	5,092	665	0	551
45+88		188	0	0	0								
	12					173	9	0	5	2,070	108	0	54
46+00		157	18	0	9								
	50					111	22	0	13	5,525	1,100	0	650
46+50		64	26	0	17								
	50					92	17	0	15	4,600	825	0	750
47+00		120	7	0	13								
	23					94	11	0	11	2,151	253	0	242
47+23		67	15	0	8								
	17					83	14	0	14	1,403	238	0	238
47+40		98	13	0	20								
	10					84	21	0	22	840	210	0	220
47+50		70	29	0	24								
	18					69	22	0	17	1,233	387	0	297
47+68		67	14	0	9								
	32					67	19	0	14	2,144	608	0	448
48+00		67	24	0	19								
	50					80	24	0	15	4,000	1,175	0	750
48+50		93	23	0	11								
	27					148	12	0	6	3,983	311	0	149
48+77		202	0	0	0								
	23					151	14	0	7	3,473	311	0	161
49+00		100	27	0	14								
	50					90	19	0	10	4,475	950	0	475
49+50		79	11	0	5								
	14					86	9	0	6	1,197	119	0	77
49+64		92	6	0	6								
	36					79	7	0	8	2,844	234	0	270