

HOT - MIX ASPHALT SURFACE COURSE, MAINLINE PAVEMENT										
LOCATION			PAVEMENT WIDTH	DISTANCE OF RUN	PAVEMENT AREA	PAVEMENT AREA	BITUMINOUS MATERIALS (PRIME COAT) 2 APPLICATIONS	AGGREGATE (PRIME COAT) 1 APPLICATION	HMA LEVELING BINDER, (MM), N70, 3/4"	HMA SURFACE COURSE, MIX "C", N70, 1 1/2"
			(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
BEGINNING OF PROJECT US 136										
STA 426+10.00	TO	STA 430+69.17	VARIES	459.17	12846.00	1427.33	1.08	2.85	59.95	119.90
STA. EQ.: STA. 430+69.17(BK) = STA. 0+00 (AHD)										
STA 0+00.00	TO	STA 10+00.00	VARIES	1000.00	47419.00	5268.78	4.00	10.54	221.29	442.58
STA 10+00.00	TO	STA 14+50.00	VARIES	450.00	12844.00	1427.11	1.08	2.85	59.94	119.88
STA 14+50.00	TO	STA 27+00.00	VARIES	1250.00	27527.00	3058.56	2.32	6.12	128.46	256.92
STA 27+00.00	TO	STA 44+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 44+00.00	TO	STA 61+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 61+00.00	TO	STA 78+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 78+00.00	TO	STA 95+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 95+00.00	TO	STA 112+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 112+00.00	TO	STA 129+00.00	22	1700.00	37400.00	4155.56	3.16	8.31	174.53	349.07
STA 129+00.00	TO	STA 134+12.27	22	512.27	11269.94	1252.22	0.95	2.50	52.59	105.19
RAILROAD OMISSION										
STA 134+82.38	TO	STA 146+00.00	22	1117.62	24587.64	2731.96	2.08	5.46	114.74	229.48
STA 146+00.00	TO	STA 149+00.00	VARIES	300.00	6606.00	734.00	0.56	1.47	30.83	61.66
STA 149+00.00	TO	STA 163+00.00	VARIES	1400.00	56081.00	6231.22	4.74	12.46	261.71	523.42
STA 163+00.00	TO	STA 169+50.00	VARIES	650.00	20023.00	2224.78	1.69	4.45	93.44	186.88
STA 169+50.00	TO	STA 180+00.00	VARIES	1050.00	27028.00	3003.11	2.28	6.01	126.13	252.26
STA 180+00.00	TO	STA 197+00.00	VARIES	1700.00	41588.00	4620.89	3.51	9.24	194.08	388.15
STA 197+00.00	TO	STA 214+00.00	24	1700.00	40800.00	4533.33	3.45	9.07	190.40	380.80
STA 214+00.00	TO	STA 231+00.00	24	1700.00	40800.00	4533.33	3.45	9.07	190.40	380.80
STA 231+00.00	TO	STA 246+40.00	24	1540.00	36960.00	4106.67	3.12	8.21	172.48	344.96
STA 246+40.00	TO	STA 248+00.00	VARIES	160.00	3950.00	438.89	0.33	0.88	18.43	36.87
STA 248+00.00	TO	STA 254+45.00	26	645.00	16770.00	1863.33	1.42	3.73	78.26	156.52
STA 254+45.00	TO	STA 255+27.47	VARIES	82.47	2718.00	302.00	0.23	0.60	12.68	25.37
STA 255+27.47	TO	STA 261+63.59	34	636.12	21628.00	2403.11	1.83	4.81	100.93	201.86
STA. EQ.: STA. 261+63.59(BK) = STA. 0+00 (AHD)										
STA 0+00.00	TO	STA 4+90.00	34	490.00	16598.00	1844.22	1.40	3.69	77.46	154.91
END OF PROJECT US 136										
IL RTE. 29 SOUTH LEG			27 & VARIES	298.60	13934.00	1548.22	1.18	3.10	65.03	130.05
IL RTE. 29 NORTH LEG			28 & VARIES	240.70	11478.00	1275.33	0.97	2.55	53.56	107.13
TOTALS =					717855.58	79761.73	60.62	159.52	3349.99	6699.99