

ILLINOIS DEPARTMENT OF TRANSPORTATION			80% FED 20% STATE TOTAL QUANTITIES	ACM M231		ACRS M232			
CODE NO	ITEM	UNIT		0005 MACON URBAN FAU 7464	0011 MACON URBAN FAU 7464	0005 MACON RURAL FAS 1536	0005 PIATT RURAL FAS 1536		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	404	101			303		
40600990	TEMPORARY RAMP	SO YD	494	314		72	108		
40603085	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N70	TON	812	812					
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	14523	4009		10139	375		
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SO YD	205	205					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	402	179		222	1		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	155607	42360		109176	4071		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	2796	2796					
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SO YD	20	20					
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	899	396		486	17		
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	289	56		233			
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	283	159		124			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2470	679		1715	76		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	6174	2295		3879			

FILE NAME =	USER NAME = teasleych	DESIGNED -	REVISED -
c:\pwork\pwork\teasleych\081214731077	196-ht-aaq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
	PLOT DATE = 10/28/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET 2	OF 6 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**		Macon, Piatt	44	4
CONTRACT NO. 74156				
ILLINOIS FED. AID PROJECT				

*125,126,126RRS-2&(126RRB
**FAS 1536 & FAU 7464