

PAVING SCHEDULE

STATION TO STATION		BITUMINOUS MATERIAL PRIME COAT	AGGREGATE PRIME COAT	LEVELING BINDER ( MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT BINDER COURSE, 1L 19-0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT PAVEMENT ( FULL-DEPTH), 14"	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	AGGREGATE WEDGE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SHOULDERS, 8"
		( GALLON)	( TON)	( TON)	( SQ YD)	( TON)	( TON)	( SQ YD)	( SQ YD)	( SQ YD)	( TON)	( TON)	( SQ YD)
258+22.0	285+56.0	1580	32	332	101		693	7898			124		1838.1
285+56.0	295+60.0	663	12	29		812	263	205	375		54		457
295+60.0	610+34.0	18185	366	3819			8318	91269			1580		
610+34.0	613+40.0	218	4	37			74			884		26	
613+40.0	614+89.0	106	2	18			36			430		13	
614+89.0	617+64.0	STRUCTURE OMISSION											
617+64.0	618+46.0	58	1	10			20			237		3	
618+46.0	619+70.0	88	2	15			30			358		17	
619+70.0	622+48.0	198	4	34			68			803		24	
622+48.0	622+77.0	17	0	4			8			84	2	2	
622+77.0	744+56.3	7037	141	1478			3227	35185			634		
744+56.3	802+74.7	3362	67	706			1412	16809					3879
802+74.7	804+99.0	130	3	27	101		59	648			12		
804+99.0	805+07.0	RAILROAD OMISSION											
805+07.0	816+92.0	685	14	144	202		315	3423			65		
	TOTALS:	32326	647	6653	404	812	14523	205	155607	2796	2470	85	6174

\*(125,126,126)RS-2&(126BR)B  
\*\*FAS 1536 & FAU 7464

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ci:\pw\work\p\dot\teasleyck\d0121473\0774156-sht-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/30/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PAVING SCHEDULE

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
••	•	Macon, Platt	44	16
CONTRACT NO. 74156			ILLINOIS FED. AID PROJECT	