

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0020		
20101000	TEMPORARY FENCE	FOOT	5626	5626		
20200100	EARTH EXCAVATION	CU YD	17163	17163		
21400100	GRADING AND SHAPING DITCHES	FOOT	50	50		
25000750	MOWING	ACRE	30	30		
28100207	STONE RIPRAP, CLASS A4	TON	252	252		
28200200	FILTER FABRIC	SQ YD	339	339		
50105220	PIPE CULVERT REMOVAL	FOOT	71	71		
54205473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	55	55		
67100100	MOBILIZATION	L SUM	1	1		
A2C020G3	TREE, CARYA CORDIFORMIS (BITTERNUT HICKORY), CONTAINER GROWN, 3-GALLON	EACH	290	290		
A2C022G3	TREE, CARYA ILLINOENSIS (PECAN), CONTAINER GROWN, 3-GALLON	EACH	290	290		
A2C050G3	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON	EACH	290	290		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0020		
A2C060G3	TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON	EACH	290	290		
A2C062G3	TREE, QUERCUS SHUMARDII (SHUMARD OAK), CONTAINER GROWN, 3-GALLON	EACH	290	290		
C2001124	SHRUB, CEPHALANTHUS OCCIDENTALIS (BUTTON BUSH), 2' HEIGHT, BALLED AND BURLAPPED	EACH	290	290		
K0029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	19	19		
K1005884	TREE TRUNK PREDATOR PROTECTION	EACH	1740	1740		
X0324079	EXISTING FIELD TILE REMOVAL	FOOT	15	15		
X2500400	INTERSEEDING, CLASS 2 (SPECIAL)	ACRE	30	30		
X2503000	MAINTENANCE MOWING	ACRE	180	180		

FILE NAME : c:\p\work\p\midat\teasley\0205341\074557-shr-aag.dgn	USER NAME : teasley	DESIGNED -	REVISED - 4/11/2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: SHEET OF SHEETS STA. TO STA.	P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	PLOT SCALE = 100.0000' / 1" =	DRAWN -	REVISED -									
	PLOT DATE = 2/1/2013	CHECKED -	REVISED -									
		DATE -	REVISED -									

* D-7 WETLAND MITIGATION 2013 CONTRACT NO. 74557
ILLINOIS FED. AID PROJECT