SEEDING AND GRADING SCHEDULE

LOCATION STATION TO STATION	SIDE	SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 1 (ACRE)	GRADING AND SHAPING FORESLOPES (SQ YD)
STA 638+33 TO STA 648+85	LT	0.19	17.1	17.1	17.1	0.19	936
	SUBTOTAL	0.19	17.1	17.1	17.1	0.19	936
	PAY TOTAL	0.25	23	23	23	0.25	936

PAVEMENT SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS MATERIALS (PRIME COAT) (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 (TON)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	AGGREGATE SHOULDERS, TYPE B (TON)
STA 624+34.70 TO STA 624+94.23	0.05	13.5		1.7
STA 638+25.97 TO STA 638+84.70	0.05	13.1		1.0
STA 648+11.00 TO STA 648+67.50	0.05	15.1		0.8
STA 648+67.50 TO STA 648+73.50			21.3	
STA 651+47.50 TO STA 651+53.50			21.3	
STA 651+53.50 TO STA 652+10.00	0.05	15.5		2.2
SUBTOTAL	0.20	57.2	42.6	5.7
PAY TOTAL	0.2	58*	43	6

* NOT A TOTAL QUANTITY

DRAINAGE SCHEDULE

LOCATION STATION	SIDE	PIPE CULVERT REMOVAL (FOOT)	METAL END SECTIONS 12" (EACH)	PIPE DRAINS 12" (FOOT)
STA 645+33	LT	12	1	12
PAY TOTAL		12	1	12

EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	SIDE	EARTH EXCAVATION FOR EROSION CONTROL (CU YD)	PERIMETER EROSION BARRIER (FOOT)	AGGREGATE (EROSION CONTROL) (TON)
STA 638+00 TO STA 638+60	RT		60	
STA 638+14 TO STA 649+26	LT		1112	
STA 638+44	RT	1.9		0.7
STA 645+15 TO STA 645+45	LT		30	
STA 647+25 TO STA 647+75	RT		50	
STA 647+58	RT	1.9		0.7
SUBTOTAL		3.8	1252	1.4
TOTAL		4	1252	2

RIPRAP SCHEDULE

LOCATION STATION	SIDE	STONE RIPRAP, CLASS A4 (SQ YD)	STONE DUMPED RIPRAP, CLASS A4 (TON)	FILTER FABRIC (SQ YD)
STA 638+44	RT		218	118
STA 645+33	LT	6		6
STA 647+58	RT		218	118
SUBTOTAL		6	436	242
PAY TOTAL		6*	436*	242*

* NOT A TOTAL QUANTITY

GUARDRAIL SCHEDULE

LOCATION GUARDRAIL STATION	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6A (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT (EACH)	GUARDRAIL REMOVAL (FOOT)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
STA 616+92 TO STA 624+83	RT					791		
STA 617+07 TO STA 618+63	LT					182		
STA 617+69.63	LT	62.5			2		4	2
STA 618+89 TO STA 624+99	LT					632		
STA 624+87.36	RT	687.5		1	1		6	1
STA 625+01.11	LT	587.5		1	1		6	1
STA 638+19.28/STA 648+68.80	RT	966	1	1			7	
STA 638+24 TO STA 648+72	RT					1053		
STA 638+32.90/STA 649+09.39	LT	985	1	1			7	
STA 638+38 TO STA 649+09	LT					1066		
STA 651+11.60	RT	25	1		1		4	1
STA 651+12 TO STA 651+66	RT					54		
STA 651+49 TO STA 652+02	LT					54		
STA 651+52.19	LT	100	1		1		4	1
PAY TOTAL		3414	4	4	6	3832	38	6

REMOVAL SCHEDULE

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	APPROACH SLAB REMOVAL (SQ YD)
STA 624+34.70 TO STA 624+58.70	75			
STA 638+60.70 TO STA 638+84.70	74			
STA 648+11.00 TO STA 648+35.00	72			
STA 648+67.50 TO STA 648+83.44		44		
STA 648+83.32 TO STA 649+21.58			39	
STA 648+83.44 TO STA 649+05.25				61
STA 651+15.59 TO STA 651+37.50				68
STA 651+37.50 TO STA 651+53.50		50		
STA 651+86.00 TO STA 652+10.00	75			
PAY TOTAL	296	94	39	129

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	URETHANE PAVEMENT MARKING - LINE 4" SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)	SKIP DASH YELLOW (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
STA 624+34.70 TO STA 631+70.00	1470.6		183.8	1	9	10
STA 631+70.00 TO STA 638+84.70	1429.0	714.7	178.7	1	8	9
STA 648+11.00 TO STA 652+10.00	798.0	399.0	99.8	2	4	6
SUBTOTAL	3697.6	1113.7	462.3	4	21	25
PAY TOTAL		5274		4	21	25