

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|--------|------------------|-------------------------------|--|--|
| CODE NO | ITEM | UNIT | | 0021 90% FED. 10% STATE | | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 12 | 12 | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 53 | 53 | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 2793 | 2793 | | |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 11968 | 11968 | | |
| 64200116 | SHOULDER RUMBLE STRIPS, 16 INCH | FOOT | 35904 | 35904 | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 | | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 28 | 28 | | |
| * 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 1436 | 1436 | | |
| * 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 35904 | 35904 | | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|-------|------------------|-------------------------------|--|--|
| CODE NO | ITEM | UNIT | | 0021 90% FED. 10% STATE | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 479 | 479 | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 35904 | 35904 | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 11968 | 11968 | | |

* SPECIALTY ITEM

| | | | | | | | | | | |
|--|-------------------------------|------------|-----------|-------------------------------------|------------------------------|-------------------------------------|----------------|--|--------------|-----------|
| FILE NAME : | USER NAME : burnsideem | DESIGNED - | REVISED - | STATE OF ILLINOIS | SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| or\p\work\p\p\dot\burnsideem\00318095\00318095.dgn | 70g00-ahp-plan.dgn | DRAWN - | REVISED - | DEPARTMENT OF TRANSPORTATION | | 761 | (101, 10211-1) | GREENS | 6 | 3 |
| | PLOT SCALE : 100.0000 ' / in. | CHECKED - | REVISED - | | | | | | | |
| | PLOT DATE : 1/14/2013 | DATE - | REVISED - | | | | | | | |
| | | | | | | SCALE: SHEET OF SHEETS STA. TO STA. | | ILLINOIS FED. AID PROJECT CONTRACT NO. 76G00 | | |