

CONSTR. CODE
STATE 100%
BOX CULVERT
0013
014-2005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
20200100	EARTH EXCAVATION	CU YD	16.5	16.5
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	20	20
40600990	TEMPORARY RAMP	SQ YD	44.4	44.4
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	36.5	36.5
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	166.9	166.9
44000100	PAVEMENT REMOVAL	SQ YD	59.6	59.6
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	267	267
44004250	PAVED SHOULDER REMOVAL	SQ YD	14.9	14.9
44201297	DOWEL BARS 1"	EACH	36	36
48101200	AGGREGATE SHOULDERS, TYPE B	TON	24.8	24.8
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5.9	5.9
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	6.7	6.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22	22
50800105	REINFORCEMENT BARS	POUND	6550	6550
50800515	BAR SPLICERS	EACH	70	70
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	205	205
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1

CONSTR. CODE
STATE 100%
BOX CULVERT
0013
014-2005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40	40
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	520	520
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	272	272
70400100	TEMPORARY CONCRETE BARRIER	FOOT	272	272
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	272	272
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	1	1
70600330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	235	235
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	3
* 78200010	BARRIER WALL REFLECTORS, TYPE B	EACH	7	7
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3
X0324762	WIDE LOAD DETOUR SIGNING	L SUM	1	1
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	333	333
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	102	102

* SPECIALTY ITEM

REV. 4-15-2019

REV. - MS

MODEL: #MODELNAME
FILE NAME: P:\111\B\BID\BID\ITEG_ILI\inois.gov\PWD\DOT\Documents\DOT_Offices\District_B\Projects\0876M15\CAD\Drawings\0876M15-sh-500.dgn

USER NAME = bergmd	DESIGNED - _____	REVISED - _____
DRAWN - _____	REVISIONS - _____	
PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = 2/7/2019	DATE - _____	REVISED - _____

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	112CLV-1	CLINTON	14	3
CONTRACT NO. 76M15			ILLINOIS FED. AID PROJECT	