



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2024

SUBJECT: FAU 2561 (Gary Avenue)
Section 20-00123-00-PV (Wheaton)
DuPage County
Contract No. 61K32
Item 007
April 26, 2024 Letting
Addendum (B)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 88 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Basis of Payment.

This work will be paid for at the contract unit price per each for UNINTERRUPTABLE POWER SUPPLY, SPECIAL or UNINTERRUPTABLE POWER SUPPLY AND CABINET, SPECIAL. Replacement of Emergency Vehicle Priority System confirmation beacons and any required modifications to the traffic signal controller shall be included in the cost of the UNINTERRUPTABLE POWER SUPPLY, SPECIAL or UNINTERRUPTABLE POWER SUPPLY AND CABINET, SPECIAL item. The concrete apron and earth excavation required shall be included in the cost of the UNINTERRUPTABLE POWER SUPPLY AND CABINET, SPECIAL item.

BICYCLE RAILING (SPECIAL)

Description: This work shall consist of furnishing and installing bicycle railing, including the in-ground post footings, as shown on the plans. The work shall conform to the applicable portions of Section 509 METAL RAILINGS of the IDOT Standard Specifications, except as modified herein.

Add the following to the end of 509.02 Materials.:

- (q) Porous Granular Backfill1003.04/1004.05
- (r) Portland Cement Concrete (Note 2) 1020

Note 2. Class SI concrete shall be used. When concrete is mixed in truck mixers or transported in agitating trucks, the time limit for unloading it may be extended to 120 minutes when approved by the Engineer.

Add the following after the first paragraph of 509.09 Method of Measurement.:

Excavation, soil disposal, porous granular backfill and concrete for the post footings will not be measured for payment.

Basis of Payment. This work will be paid for at the contract unit price per foot for BICYCLE RAILING (SPECIAL).

CONCRETE CURB, TYPE B (SPECIAL)

Description. This work shall consist of constructing a reinforced concrete curb with a variable depth, abutting new concrete sidewalk, with the exposed face of curb greater than 12 inches as shown in the plans or as directed by the Engineer. The reinforced concrete curb shall be installed on a compacted aggregate base course in accordance with Section 311 of the Standard Specifications.

General. The work shall be performed in accordance with Section 606 of the “Standard Specifications”, IDOT Standard Drawing 606001, the plan detail, and as specified herein. The face of curb shall be constructed with variable exposed height from the surface of the proposed sidewalk to the surface of the adjacent existing ground.