



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 9, 2024

SUBJECT FAP Route 327 (US 50)  
Project NHPP-0BPJ(861)  
Section (3,2B) B-1  
Lawrence County  
Contract No. 74443

Item No. 99, April 26<sup>th</sup>, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i of the Table of Contents of the Special Provisions.
2. Revised pages of 10 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

|   |    |
|---|----|
| LOCATION OF PROJECT .....                                   | 1  |
| DESCRIPTION OF PROJECT .....                                | 1  |
| TRAFFIC CONTROL PLAN .....                                  | 1  |
| BORROW AREAS, USE AREAS, AND/OR WASTE AREAS .....           | 5  |
| CHANGEABLE MESSAGE SIGNS .....                              | 6  |
| CLASS BS AGGREGATE OPTIMIZATION .....                       | 6  |
| EMBANKMENT .....  | 6  |
| FILLING INLETS, SPECIAL .....                               | 7  |
| HMA SURFACE REMOVAL .....                                   | 8  |
| HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.....        | 8  |
| LINEAR DELINEATION PANELS .....                             | 8  |
| PLUG EXISTING PIPE .....                                    | 9  |
| <del>REMOVAL OF EXISTING STRUCTURES</del> .....             | 10 |
| SEEDING, CLASS 2 (SPECIAL) .....                            | 10 |
| STATUS OF UTILITIES TO BE ADJUSTED .....                    | 10 |
| TRAFFIC BARRIER TERMINALS .....                             | 11 |
| REMOVAL OF EXISTING STRUCTURES .....                        | 11 |
| SLIPFORM PARAPET .....                                      | 12 |
| BRIDGE DECK CONSTRUCTION .....                              | 16 |
| HOT DIP GALVANIZING FOR STRUCTURAL STEEL.....               | 17 |
| PREFORMED PAVEMENT JOINT SEAL.....                          | 21 |
| BAR SPLICERS, HEADED REINFORCEMENT .....                    | 27 |
| AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....             | 28 |
| CEMENT, TYPE IL (BDE).....                                  | 29 |
| COMPENSABLE DELAY COSTS (BDE).....                          | 29 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... | 32 |
| FUEL COST ADJUSTMENT (BDE).....                             | 41 |
| HOT-MIX ASPHALT (BDE).....                                  | 43 |
| PERFORMANCE GRADED ASPHALT BINDER (BDE).....                | 44 |
| PORTLAND CEMENT CONCRETE (BDE) .....                        | 48 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....    | 49 |
| SEEDING (BDE) .....   | 50 |
| SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....       | 55 |
| SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) .....       | 57 |
| STEEL COST ADJUSTMENT (BDE).....                            | 58 |



**REMOVAL OF EXISTING STRUCTURES**

~~The removal and satisfactory disposal of existing SN 051-0009 shall be according to Section 501 of the Standard Specifications and as described in the plans. The work shall include the staged removal of the steel bridge rail, wearing surface, superstructure, approach spans, and all four concrete wing walls. The sequence of removal shall be as detailed in the structure plans.~~

~~All work described shall be paid for at the contract unit price per EACH for REMOVAL OF EXISTING STRUCTURES with no additional compensation. The quantity of each shall include both stage I and stage II removal.~~

**SEEDING, CLASS 2 (SPECIAL)**

All areas disturbed during construction shall be seeded with class 2 seeding in accordance with Section 250 of the Standard Specifications. All disturbed areas shall be covered with mulch in accordance with Section 251 of the Standard Specifications. The Contractor shall use method 1.

This work will be paid for at the contract unit price per ACRE for SEEDING, CLASS 2 (SPECIAL), which price shall include furnishing and applying fertilizer nutrients at the rate of 90 lbs./acre for Nitrogen, Phosphorus, and Potassium; at the rate of 4 tons/acre for agricultural ground limestone; and at the rate of 2 tons/acre for mulch.

**STATUS OF UTILITIES TO BE ADJUSTED**

The following utilities are involved in this project. The utility companies have provided the estimated dates.

| <u>Name/Address of Utility Company</u>   | <u>Type</u> | <u>Location of conflict</u> | <u>Est. Date of Relocation</u> |
|--|-------------|-----------------------------|--------------------------------|
| CMS-Dolt<br>Att: Steve Creasey<br>Email: Steve.Creasey@illinois.gov<br>Phone: 217-558-1176 | Fiber       | Contact Info Only           |                                |
| IL Gas<br>Att: Jordan Kocher<br>Email: jkocher@ilgas.com<br>Phone: 618-395-8588            | Gas         | Contact Info Only           |                                |

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Section 102, and Articles 105.07, 107.20, 107.31, and 108.02 of the Standard Specifications for Road and Bridge Construction shall apply.

The estimated utility relocation dates should be part of the progress schedule submitted by the Contractor. If any utility adjustments or relocations have not been completed by the above dates specified and when required by the Contractor's operations after these dates, the Contractor