





- FINAL TURF RESTORATION WILL BE PROVIDED BY CONTRACTOR RESTORATION TO MATCH TURF RESTORATION PROVIDED BY CONTRACTS #62593 & #62304.
- PLAN REFLECTS CONTRACTS #62593 & #62304 AS EXISTING CONDITIONS.

## **LEGEND:**



TEMPORARY EROSION CONTROL SEEDING (100 LBS PER ACRE) SEDIMENT CONTROL, SILT FENCE



INLET FILTER, TO BE INSTALLED IN OFF PROJECT DRAINAGE STRUCTURES ACCEPTING STORMWATER RUNOFF



TEMPORARY DITCH CHECK





63RD 71ST 79TH 87TH LOCATION MAP

SCALE: 1" = 20'-0" ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94 (DAN RYAN EXPRESSWAY)

I-57 to 71st STREET EROSION CONTROL PLAN
NB I-57 AND NB I-94, NB I-57
STA. 253+00.00 TO NB I-94 STA. 2207+00.00 60EF2 DRAWN BY:

DATE: JANUARY 9, 2007

TYLININTERNATIONAL

SHEET 10 OF 27