

ROUTE NO.	SECT.	COUNTY		SHEET NO,	TOTAL SHEETS
F.A.I. 39	201- IBR	WINNEB	NGO	24	40
FED. ROA NO.	DIST. 7	ILLINOIS	FED. AID PROJECT		

CONTRACT NO 64857

 $^{3}_{4}" \phi$ Aluminum Bar. See Top Plan - New

⁷₁₆ "x¹₄" Aluminum Bar. See Top Plan - New

Sealant Sikabond Construction Adhesive or Approved Equal

BILL OF MATERIAL

Item	Unit	Stage 1 S.B.	Stage 2 N.B.	Total Quantity
Floor Drains (Special)	Each	128	128	256
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.	100	100	200

NOTES:

The quantity for Structural Repair of Concrete is an estimated quantity. Limits of concrete repair shall be measured by the Contractor, approved by the Engineer and paid for at the Contract unit price for "Structural Repair of Concrete (Depth Equal to or Less Than 5")".

The cost of preparation, materials, clean up, labor and equipment necessary for installation of the described floor drain assembly shall be paid for at the contract unit price for "Floor Drains (Special)".

Dimensions of existing floor drains are from existing plans. The Contractor shall verify the dimensions in the field prior to fabrication of the new floor drain assembly.

Areas of reinforcement to be replaced as described in "Structural Repair of Concrete" shall be determined by the Contractor and approved by the Engineer.

REVISION	DATE		DESCRIPTION					
STATE OF ILLINOIS								
Di	DEPARTMENT OF TRANSPORTATION							
FLOOR DRAIN DETAILS								
I-3	I-39 (FAI 39) OVER KISHWAUKEE RIVER							
SECTION 201-1BR WINNEBAGO COUNTY								
STATION 2425+00								
STRUCTURE NOS. 101-0133 (S.B.) & 101-0134 (N.B.)								
PARSONS			CHICAGO, ILLINOIS					
DRAWING NO. 24	SCALE N.T.S	-	DATE FEB 2007	SHEET NO. S-13				