			CON	ILW	Č1 NO.	Tossa
F.A RTE.	SECTION	С	OUNT	Y	TOTAL SHEETS	SHEET NO.
789	*		MADIS	QΝ	_42_	28
STA.		то	STA			
FED. RO.	AD DIST. NO	ILLINOIS	FED.	AID	PROJECT	

• 125RS-1, 125I-2TS-2

ELECTRICAL GENERAL NOTES

- 1. ALL VEHICLE AND PEDESTRIAN SIGNAL HEADS SHALL HAVE 12" SECTIONS. MOUNTING HARDWARE SHALL BE UNPAINTED ALUMINUM. ALL BOLTS, SCREWS, NUTS AND WASHERS SHALL BE STAINLESS STEEL. ANTI -SEIZE PASTE COMPOUND SHALL BE USED ON ALL MOUNTING HARDWARE FIELD CONNECTIONS.
- 2. BACK PLATES SHALL BE ABS PLASTIC.
- 3. THE CONTROLLER CABINET SHALL BE UNPAINTED ALUMINUM.
- 4. THE LOCATION OF MAST ARM SUPPORTS SHALL BE APPROVED BY THE ENGINEER BEFORE FOUNDATIONS ARE CONSTRUCTED, MAST ARM POLES SHALL BE LOCATED A MINIMUM OF 10 FEET FROM THE EDGE OF PAVEMENT OR 2 FEET FROM THE EDGE OF SHOULDER, WHICHEVER DISTANCE IS GREATER. IN CURBED SECTIONS, THE MAST ARM POLES SHALL BE LOCATED A MINIMUM OF 5 FEET FROM THE FACE OF THE CURB. THESE DISTANCES ARE TO THE NEAR FACE OF THE MAST ARM POLE.
- 5. ALL TRAFFIC SIGNAL CABLES SHALL BE #14 AWG STRANDED COPPER UNLESS OTHERWISE SPECIFIED, TERMINAL ENDS SHALL HAVE CRIMPED- ON RING TONGUE CONNECTORS.
- 6. THE LOCATION OF ALL DETECTOR LOOPS SHALL BE APPROVED BY THE ENGINEER BEFORE ANY SLOTS ARE SAWED IN THE PAVEMENT.
- DETECTOR LOOP LEAD- IN SPLICES SHALL BE MADE IN A HAND HOLE PER SECTION 873 OF THE STANDARD SPECIFICATIONS. CONDUCTORS SHALL BE SPLICED IN A RIGID MOLD FILLED WITH NON -HARDENING EPOXY FILLER. ROSIN- CORE SOLDER SHALL BE USED.
- 8. CALL DELAY SHALL NOT FUNCTION WHEN THE RELATED PHASES ARE IN THE
- 9. CALL CARRYOVER SHALL FUNCTION ONLY WHEN THE RELATED PHASES ARE
- 10. ALL INDUCTIVE LOOP DETECTORS SUPPLIED FOR THIS PROJECT SHALL HAVE THE CAPACITY OF OPERATING WITH BOTH DELAY AND EXTENSION MODES ACTIVE, IF A TIME SETTING IS PROGRAMMED. THEY SHALL BE RACK MOUNTED.
- 11. ALL HAND HOLES SHALL BE CAST-IN-PLACE PORTLAND CEMENT CONCRETE (PER ARTICLE 814.03(b)). THE CAST IN PLACE LEGEND IN THE COVER SHALL BE "TRAFFIC SIGNALS". SLOPE HAND HOLE COVERS TO MATCH PROPOSED GRADE FLEVATIONS.
- 12. ACTUAL DEPTHS OF THE CONCRETE FOUNDATIONS FOR THE MAST ARM SUPPORT POLES ARE AS FOLLOWS:


NE CORNER, 32' M.A.: 11'-0" DEEP NW CORNER, 42' M.A.: 13'-0" DEEP SE CORNER, 32' M.A.: 11'-0" DEEP SW CORNER, 32' M.A.: 11'-0" DEEP

THESE DEPTHS ARE DETERMINED BY THE DEPARTMENT FROM THE SOIL BORING DATA.

- 13. DETECTORS LOOPS SHALL BE PLACED IN THE BINDER COURSE PRIOR TO INSTALLING BITUMINOUS SURFACE COURSE
- 14. THE CONTRACTOR SHALL INSTALL FOUR (4) GROUND RODS (3/4" X 12') AND #6 AWG BARE COPPER GROUND CONDUCTORS IN THE CONTROLLER FOUNDATION AS PER THE SPECIAL PROVISION, " CONCRETE FOUNDATION, TYPE D".
- 15. NO SERVICE POLE SHALL BE LOCATED CLOSER THAN 10' MEASURED FROM THE EDGE OF PAVEMENT FROM FAP ROUTE 789 (IL-143).
- 16. ANCHOR BOLTS, NUTS, AND WASHER REQUIRED WITH TYPE D FOUNDATION SHALL BE INCLUDED IN THE PAY ITEM, "CONCRETE FOUNDATION, TYPE D".
- 17. AN UNDERGROUND "CABLE MARKING TAPE" SHALL BE INSTALLED WITH ALL TRENCH & BACK FILL FOR ELECTRICAL WORK IN ACCORDANCE WITH THE ARTICLES 815.03 (d) & 1066.05 OF THE STANDARD SPECIFICATIONS.
- 18. CENTER TO CENTER DISTANCE BETWEEN THE CONDUITS, WHERE TWO OR MORE LOOP LEAD -IN CONDUITS ARE INSTALLED FROM THE EDGE OF THE PAVEMENT TO THE NEAREST HAND HOLE, SHALL BE SIX INCHES MINIMUM AT THE EDGE OF THE PAVEMENT.
- 19. LOCATE UNDERGROUND CABLES PRIOR TO ATTEMPTING TO CONSTRUCT THIS PROJECT.
- 20. A 9-1-1 ADDRESS TO OBTAIN THE ELECTRICAL SERVICE AT THIS LOCATION IS "15-1-09-31-00-000-001.003. FOR FURTHER ASSISTANCE, PLEASE CALL MR. WILLIAM H. GAMBLIN, 9-1-1 COORDINATOR, MADISON COUNTY. HIS CONTACT NUMBER IS (618) 296-5900.
- 21. PORTABLE CHANGEABLE MESSAGE SIGNS SHALL REMAIN IN OPERATION 72 HOURS PRIOR TO AND 72 HOURS AFTER THE TRAFFIC SIGNAL TURN ON.

LOOP	PHASE (Ø)	LOOP SIZE(FT)	REOUIRED * OF TURNS	CALCULATED INDUCTANCE MICROHENRIES (4H)	CALCULATED RESISTANCE OHMS (12)
EB_CCQ	6	6_X_6	7	494	3.32
EB_IHRU_LN	6	6_X_50	_3-6-3_	853	3.11
EB_LI	1	6_X_50	3:6:3	<u>853</u>	<u>3.1</u> 1
EB_BI	6	6_X_3Q	3:6:3	557	2.60
\$B_IHRU_LN	8	6_X_5Q	_3:6:3_	803	1.97
SB_RI_LN_	8	6_X_4Q	_3:6:3_	647	1,55
WB_CCO_THRU	2	6_X_6	7	525	4,00
WB_CCO_LI	5	_6_X_6	7	525	4.00
WB_IBRU_LN	2	6_X_50	3:6:3	827	2.52
WB_LI_LN	5	_6_X_50	3:6:3	821	2,52
WB_RI_LN	2	6_X_3Q	3-6-3	519	1,74
NB_IHRU	4	6_X_50	3:6:3	855	3.16
NB_RI	4	_6 X 40	<u>3-6-3</u>	702	2.79

THE ABOVE VALUES ARE CALCULATED OF COMBINED LOOP AND LEAD-IN INDUCTANCE AND RESISTANCE. ACTUAL MEASURED VALUES SHOULD BE WITHIN +/- 20% OF THESE





SEC. E-E

* LIMITS OF "TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)"

DETAIL

TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL) (NO SCALE)





DETAIL HANDHOLE TO INTERCEPT EXISTING CONDUIT* * NOT A PAY ITEM

- 1. REMOVAL OF EXISTING CONDUIT FROM THE HANDHOLE AND THE INSTALLATION OF THE CONDUIT BUSHING SHALL BE INCIDENTAL TO THE HANDHOLE.
- THE CONTRACTOR SHALL BE PAID TO LOCATE THE CONDUIT UNDER OTHER PROVISIONS OF THIS CONTRACT. SEE LOCATING UNDERGROUND CABLE IN THE STANDARD SPECIFICTIONS.

TRAFFIC SIGNALS LEGEND

PROPOSED CONTROLLER

PROPOSED PEDESTRIAN PUSHBUTTON DETECTOR

PROPOSED STREET NAME SIGN/TRAFFIC SIGN

PROPOSED SIGNAL POST WITH BACKPLATE

PROPOSED CONDUIT: "T" TRENCH, "P" PUSH, SIZE SPECIFIED

PROPOSED SIGNAL HEAD, PEDESTRIAN

PROPOSED ILLUMINATED SIGN

PROPOSED SIGNAL POST

PROPOSED SERVICE INSTALLATION

EMERGENCY VEHICLE PRIORITY SYSTEM

GSC	GALVANIZED STEEL CONDUIT
PVCC	POLYVINYL CHLORIDE CONDUIT
UD .	UNIT-DUCT
$\bigcirc \rightarrow \bigcirc$	EXISTING SIGNAL POST
O+D	EXISTING SIGNAL POST WITH BACKPLATE
<u>4</u> 4	EXISTING TRAFFIC SIGNAL MAST ARM
	EXISTING HANDHOLE
	EXISTING DOUBLE HANDHOLE
H	EXISTING HEAVEY DUTY HANDHOLE
	EXISTING DETECTOR LOOP
\bowtie	EXISTING CONTROLLER
O	EXISTING STREET NAME SIGN/TRAFFIC SIGN
	EXISTING ILLUMINATED SIGN
-[]-	EXISTING SERVICE INSTALLATION
\ll	EXISTING EMERGENCY VEHICLE SYSTEM DETECTOR (E.V.P.S.)
	EXISTING (E.V.P.S.) CONFIRMATION BEACON
-	EXISTING SIGNAL HEAD, PEDESTRIAN
0	EXISTING PEDESTRIAN PUSHBUTTON DETECTOR
	EXISTING GALVANIZED STEEL CONDUIT
	PROPOSED SIGNAL HEAD WITH BACKPLATE, MAST ARM MOUNTED
•	PROPOSED EMERGENCY VEHICLE SYSTEM DETECTOR (E.V.P.S.)
-X	PROPOSED (E.V.P.S.) CONFIRMATION BEACON
	PROPOSED HANDHOLE
	PROPOSED DOUBLE HANDHOLE
Н	PROPOSED HEAVEY DUTY HANDHOLE
	PROPOSED DETECTOR LOOP

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION	-
NAME DATE	ILLINOIS DEFARTMENT OF TRANSPORTATION	
	ELECTRICAL GENERAL NOTES,	
	LEGEND, AND DETAILS	
	FAP ROUTE 789	
	SECTION 125RS-1, 125I-2TS-2	
	COUNTY MADISON	
	SCALE: HORIZ. DRAWN BY	
	DATE CHECKED BY	

DATE VAME SCALE ENCE