ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

·	30WWANT OF	~ ~	IVIAU			CODE
	SUMMARY OF QUANTITIES		URBAN 100 1-MCHD	CONSTRUCTION TYPE CODE SFTY-2A		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	5. v. =		
50501130	STRUCTURAL STEEL REPAIR	POUND	440	440		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	LSUM	1	1		-
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
Z0003600	BEAM STRAIGHTENING	L SUM	. 1	1		
					. ,	general control
				-		
			-			
		:				

| CONTRACT NO. 76A40 | F.A.I. | SECTION | COUNTY | TOTAL | SHEET | NO. | SHEETS | NO. | SHEET | SHEET | SHEET | NO. | SHEET | SHEET | SHEET | NO. | SHEET | SHEET | NO. | SHEET | SHEE

STA. TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, GENERAL NOTES, STANDARDS & SUMMARY OF QUANTITIES
- 3-4. BRIDGE REPAIR PLANS

HIGHWAY STANDARDS

000001_04

701400-02

701406--04 702001--06

GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
- ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING, FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY, AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * AMERENIP (GAS & ELECTRIC)
 - * CENTERPOINT ENERGY (PIPELINE)
 - * CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - * CONSOLIDATED COMMUNICATIONS (COMMUNICATIONS)
 - * VILLAGE OF GLEN CARBON (WATER & SANITARY SEWER)
 - . AT&T ILLINOIS (COMMUNICATIONS)
 - * LEVEL 3 COMMUNICATIONS (COMMUNICATIONS)

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)

- 3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 4. NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING, TOPOGRAPHY, ETCETERA SHOWN IS APPROXIMATE AND WAS CREATED USING MICROFILM.
- ONE CHANGEABLE MESSAGE SIGN SHALL BE REQUIRED ON THE PROJECT. THE MESSAGE SIGN SHALL BE PLACED TWO
 WEEKS BEFORE ANY LANE RESTRICTION. THE MESSAGE SIGN SHALL BE PLACED ALONG WESTBOUND 1–270, JUST WEST
 OF THE IL 159 RAMP.
- 6. NO OVERNIGHT LANE CLOSURES WILL BE PERMITTED ON 1-270.
- "ROAD CONSTRUCTION AHEAC" SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT AND ON THE WESTBOUND ENTRANCE RAMP FROM IL 159, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
- 8. THE CONTRACTOR SHOULD INSURE THAT, IN AND ADJACENT TO WORK AREAS, ALL LOOSE, SPALLED AND DELAMINATED CONCRETE IS REMOVED PRIOR TO REOPENING LANES TO TRAFFIC. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCIDENTAL TO "BEAM STRAIGHTENING".
- 9. IF THE CONTRACTOR CHOOSES TO USE TRAFFIC CONTROL ON MERIDIAN ROAD, IT WILL BE AT THERE COST.