

SEE DIST. 5 DETAIL C-1.14

SEE ENTRANCE TYPICAL SECTIONS (SHEET 5 OF 5)

STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT-+02.93 12.07' LT. CONTRACT NO.: 91358 PCC MAILBOX TURNOUT-+90.83 22.00' LT. PCC DRIVEWAY PAVT 6 PR. C. BOWMAN AVE. MATCH IN 40.83 ALONG ENTRANCE & +74.65 30.84' LT. PCC DRIVEWAY PAVT 6 -PCC DRIVEWAY PAVT 6 RELOCATED MAILBOX +39.82 13.24' LT. PCC MAILBOX TURNOUT -PR. CURB OUTLET +39.82 17.74' LT. PR. C&G TY. B-6.24 PRIVATE ENTRANCE DETAIL (P.E.) 68+86.99 NOTES THE TEMPORARY RELOCATION OF EXISTING MAILBOX SHALL BE IN ACCORDANCE WITH ARTICLE 107.20 OF THE STANDARD SPECIFICATIONS. ENTRANCE SIDESLOPES SHALL BE CONSTRUCTED TO VARIES 12.07' TO 22.00' ±10.00' VARIES 13.24' TO 12.07' PR. ¢ BOWMAN AVE. 2.00 MAILBOX POST ⅓ IN/FT 1/2IN/FT EXISTING GROUND PCC DRIVEWAY PAVEMENT 6" SECTION A-A SHEET 4 OF 5 CITY OF DANVILLE, ILLINOIS WINTER AVENUE RECONSTRUCTION ENTRANCE DETAILS

SCALE: 1" = 10'

DRAWN BY: TON

DATE: 12/21/06

CHECKED BY: MBF