



NOTES:

f'c = 3500 psi fy = 60,000 psi (REINF.)

AVOID REINFORCEMENT WHEN SPACING RAIL ANCHOR ASSEMBLY.

SEE "BICYCLE RAILING DETAILS" SHEET FOR RAILING DETAILS.

BARRIER RAILING SHALL NOT BE QUANTIFIED SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE INSTALLATION AND COST OF BICYCLE RAILING.

BARS d1 & d2 SHALL BE CAST IN PCC SIDEWALK 5", SPECIAL

CONCRETE BARRIER WALL

(WEST END)

BILL OF MATERIAL

ReInforcement Bars, Pound 310
Epoxy Coated Concrete
Structures Cu. Yds. 3.2
Protective Coat Sq. Yds. 24

 st not a total quantity. (For total quantity add similar pay items).

REVISIONS
NAME
DATE
WINTER AVENUE RECONSTRUCTION
BICYCLE PATH DETAILS
WEST END

SCALE: N.T.S. DATE: 12/21/06
DRAWN BY: ACW CHECKED BY: MBF