


PLAN









GENERAL NOTES:

- 1. ALL EXCAVATION SHALL BE KEPT DEWATERED DURING CONSTRUCTION OPERATIONS UNTIL BACKFILL
- ALL WORK WILL BE DONE IN ACCORDANCE WITH "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS." CURRENT EDITION.
- 3. SANITARY SEWER PIPE SHALL MEET ASTM D3034 AND SHALL BE TYPE SDR 35, 8" NOMINAL DIAMETER WITH INTEGRAL BELL AND ELASTOMERIC GASKETS MEETING ASTM D3212 AND ASTM F477. UNLESS OTHERWISE NOTED.
- 4. BACKFILL SHALL MEET STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS AND SHALL BE CA-15, CA-16, CM-15 OR CM-16 FOR BEDDING (BEDDING CLASS I AS PER ASTM D2321) AND SELECT GRANULAR MATERIAL EXCEPT THAT THE TOP 12 INCHES SHALL BE CA-6, WHERE SELECT GRANULAR
- 5. WATER AND SEWER MAIN SEPARATION WILL BE PER "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS," CURRENT EDITION.
- 6. AIR TESTING AND DEFLECTION TESTING SHALL BE PERFORMED ACCORDING TO "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS," SECTION 31-1.11.


			THRUS	T BLOC	K DIME	NSIONS				
D	A	В	С	E	F	G	Н	J	К	L
4" & 6"	8′′	11"	1'-3"	8"	8''	8"	3''	2'-6''	2'-6"	3'-0''
8"	9''	1'-2''	1'-8"	9"	10''	9"	3′′	3'-0"	2'-9"	4'-0"
10"	10"	1'-6''	2'-1"	10"	1'-0"	1'-0"	3′′	4'-0"	3'-0"	4'-6"
12"	1'-0"	1'-8''	2'-6"	11''	1'-3"	1'-0''	3''	4'-6"	3'-6"	4'-9"
16"	1'-2"	2'-4"	3'-4"	1'-3"	1'-8"	1'-4"	4"	5'-2"	4'~0"	6′-6′′
20"	1'-3"	3'-0"	4'-2"	1'-6"	2'-1"	1'-9"	4''	5'-6"	4'-9''	8'-0"
24"	1'-4"	3′-6"	5'-0"	1'-8''	2'-6"	2'-0"	5''	6'-0"	5'-6"	9'-6"
MINIMUM REQUIRED BEARING DIMENSIONS.										





THRUST BLOCK DETAIL

SECTION COUNTY 8419 99-00048-01-PV FAYETTE 142 STA TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 95500



BEDDING

BEDDING PER SPECIFICATIONS REQUIRED IN ALL LOCATIONS WHERE SEWER IS WITHIN TWO (2) FEET OF A PERMANENT SURFACE. CASE I BACKFILL FREE FROM ORGANICS AT ALL OTHER LOCATIONS. (INCLUDED IN THE COST OF PIPE)

HAUNCHING

HAUNCHING PER SPECIFICATIONS REQUIRED IN ALL LOCATIONS WHERE SEWER IS WITHIN TWO (2) FEET OF A PERMANENT SURFACE. CASE I BACKFILL FREE FROM ORGANICS AT ALL OTHER LOCATIONS. (INCLUDED IN THE COST OF PIPE)

INITIAL BACKFILL INITIAL BACKFILL PER SPECIFICATIONS REQUIRED IN ALL LOCATIONS WHERE SEWER IS WITHIN TWO (2) FEET OF A PERMANENT SURFACE. CASE I BACKFILL FREE. FROM ORGANICS AT ALL OTHER LOCATIONS. (INCLUDED IN THE COST OF PIPE)

FINAL BACKFILL

SELECT GRANULAR BACKFILL PER SPECIFICATIONS REQUIRED IN ALL LOCATIONS WHERE THE EDGE OF THE SEWER TRENCH IS LOCATED WITHIN TWO (2) FEET OF A PERMANENT SURFACE (ELIGIBLE FOR PAYMENT). CASE I BACKFILL FREE FROM ORGANICS AT ALL OTHER LOCATIONS

TRENCHING DETAIL

REVISIO	NS	ILLINOIS DEPARTMENT OF TRANSPORTATION						
NAME	DATE	TEETINGS DEFAITIMENT OF TRANSFORTATION						
		TYPIAN CEWED DETAILS						
		TYPICAL SEWER DETAILS						
-10	_							
		SCALE: VERT. DRAWN BY KOJ						
		HORIZ.						