TOTAL SHEET SHEETS NO. SECTION COUNTY CONTRACT NO. 97296 TRAFFIC CONTROL PLAN STRUCTURE & ROADWAY CONSTRUCTION STA 446+00 TO STA 450+00 (NOT TO SCALE) ROAD ROAD ROAD CLOSED CLOSED CLOSED 500 FT 500 FT AHEAD W20-3 W20-3 W20-3 FRUIT ROAD TYPE III BARRICADES
WITH ROAD CLOSED
SIGNS R-11-2 4830 TYPE III BARRICADES WITH ROAD CLOSED SIGNS R-11-2 4830 THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER 72 HOURS PRIOR TO CLOSURE.
 ALL TRAFFIC CONTROL DEVICES SHALL BE REFLECTIVE AND INCLUDE LOW INTENSITY FLASHING LIGHTS.
 LOCATION OF TRAFFIC CONTROL DEVICES SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT.
 THE CONTRACTOR SHALL MAINTAIN TEMPORARY ACCESS TO DRIVEWAYS AFFECTED BY CONSTRUCTION.
 FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.
 TRAFFIC CONTROL SHALL CONFORM TO IDOT HIGHWAY STANDARDS: 702001-06, B.L.R. 21-6

ROAD CLOSED AHEAD

W20-3

ROAD

CLOSED

AHEAD

W20-3

NOTES:

FRUIT ROAD

CLOSED **AHEAD**