INDEX OF SHEETS

- COVER SHEET, SHEET INDEX, & HIGHWAY STANDARDS
- 2. SUMMARY OF QUANTITIES, & GENERAL NOTES
- 3. TYPICAL SECTIONS
- 4.-5. SCHEDULES OF QUANTITIES
- 6. TRAFFIC CONTROL PLAN
- 7. PLAN/PROFILE SHEET
- 8. GENERAL STRUCTURE PLAN
- 9.-10. SUPERSTRUCTURE DETAILS
- 11. BEAM DETAIL
- 12. ABUTMENT DETAIL
- 13. PIER DETAIL
- 14. BRIDGE RAIL DETAIL
- 15. NAME PLATE DETAIL
- 16. ENCASEMENT DETAIL
- 17. EROSION CONTROL PLAN 18.-28. CROSS SECTION SHEETS


HIGHWAY STANDARDS

000001-04 280001-03 515001-02 630001-07 630301-04

631032-03 635006-02 635011-01 666001

702001-06 B.L.R. 21-6


J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

BRIDGE REPLACEMENT AND REHABILITATION PROGRAM
PLANS FOR PROPOSED
MADISON COUNTY
SECTION 04-00176-00-BR
FAS 766 FRUIT ROAD
OVER SUGAR FORK CREEK
MARINE & ALHAMBRA TOWNSHIPS
PROJECT BRS-0766(103)


EXISTING STRUCTURE: S.N. 060-3045, BUILT IN 1954,
4 PANELS @ 70-0' c. TO c. END BEARINGS, 20-0' o. TO c.
WIDTH, PRAIT PONY TRUSS - RIVETED, SINGLE-SPAN.



THESE PLANS WERE PREPARED BY ME OR BY A FULL TIME MEMBER OF MY STAFF WORKING UNDER MY PERSONAL SUPERVISION.

For J Stull 1-23-07
GARY O STAHLHUT, P.E. No. 062-041472 DATE

MADISON COUNTY HIGHWAY DEPARTMENT 7037 MARINE ROAD EDWARDSVILLE, IL 62025 PHONE: (618) 692-7040 FAX: (618) 692-7049



PROPOSED STRUCTURE: S.N. 060-3343, 3-SPAN

PRECAST PRESTRESSED CONCRETE DECK BEAMS UPON SPILL-THRU ABUTMENTS WITH STEEL H BEAM PILING

LOCATION MAP

SCALE: 1" = 2,000'

NET LENGTH OF PROJECT: 400 FT (0.076 MI)

DESIGN DESIGNATION: RURAL TWO-LANE LOCAL ROAD


FUNCTIONAL CLASSIFICATION: COLLECTOR

DESIGN SPEED: 50 MPH

2006 ADT = 325

RTE. SECTION COUNTY TOTAL SHEET NO. SHEETS NO. SECTION RADISON 26 4

CONTRACT NO. 97296
FEDERAL AID PROJECT



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Approved 1-23-07

Passed 1-29.07

OLIMIN OBLITUDO
IDistrict & Engineer of Local Roads & Streets

Releasing for Bid Based on Limited

1-29-07

Mary Comments Engineer

ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	72
20200100	EARTH EXCAVATION	CU YD	846
20400800	FURNISHED EXCAVATION	CU YD	384
25000200	SEEDING, CLASS 2	ACRE	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
25100120	MULCH, METHOD 2	TON	1
25100630	EROSION CONTROL BLANKET	SQ YD	314
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50
28000300	TEMPORARY DITCH CHECKS	EACH	4
28000400	PERIMETER EROSION BARRIER	FOOT	300
28100107	STONE RIPRAP, CLASS A4	SQ YD	554
28200200	FILTER FABRIC	SQ YD	554
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	380
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	51
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50300225	CONCRETE STRUCTURES	CU YD	42.4
50300280	CONCRETE ENCASEMENT	CU YD	18.5
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2970
50800105	REINFORCEMENT BARS	POUND	5320
509010 <i>50</i>	STEEL RAILING TYPE SM	FOOT	180
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1240
51202305	DRIVING PILES	FOOT	1240
51203400	TEST PILE STEEL HP10X42	EACH	2
51500100	NAME PLATES	EACH	1
542C1069	PIPE CULVERT, CLASS C, TYPE 2, 24"	FOOT	36
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	330
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	900
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
78200410	GUARD RAIL MARKERS, TYPE A	EACH	8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
X5020501	UNDERWATER STRUCTURE EXCAV PROTECTION - LOCATION 1	EACH	1

| RTE. | SECTION | COUNTY | TOTAL SHEET | NO. | FAS 766 | 04-00176-00-BR | MADISON | 26 | 2

GENERAL NOTES

CONTRACT NO. 97296

- 1. THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007", AND SPECIAL PROVISIONS.
- 2. THE CONTRACTOR SHALL BE REQUIRED TO COMPLY WITH THE PROVISIONS OF THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) STORM WATER PERMIT AND IMPLEMENT THE EROSION CONTROL PLAN INCLUDED IN THESE PLANS, AS SPECIFIED IN ARTICLE 107.23, THE ENGINEER MUST GIVE PRIOR APPROVAL BEFORE DISTURBANCE OF ANY AREA CAN BEGIN.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATION, THE J.U.L.I.E. NUMBER IS 1-800-892-0123.

THE LOCATION OF ALL UTILITIES ARE BASED ON INFORMATION PROVIDED BY OTHERS AND ARE INTENDED TO BE APPROXIMATE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE HIS CONSTRUCTION ACTIVITIES WITH THE VARIOUS UTILITY OWNERS. ALL POTENTIAL CONFLICTS SHALL BE INVESTIGATED AND REMEDIAL ACTION TAKEN PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS.

ALL UTILITY FACILITIES THAT REQUIRE RELOCATION WITHIN COUNTY R.O.W. SHALL BE COMPLETED BY THE UTILITY COMPANY UNLESS OTHERWISE SHOWN ON THE PLANS.

- 4. IN ADDITION TO FIELD SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- 5. ALL STATION AND OFFSET REFERENCES ARE TO THE SECTION LINE, WHICH IS ALSO THE PROPOSED ROADWAY CENTERLINE, UNLESS OTHERWISE NOTED. THE STATE PLANE COORDINATE SYSTEM HAS BEEN USED FOR THE HORIZONTAL CONTROL.
- 6. ALL ELEVATIONS SHOWN ON THE PLANS ARE BASED ON U.S.G.S. MEAN SEA LEVEL DATUM.
- 7. ANY REFERENCE WITHIN THESE PLANS TO A STANDARD SHALL BE INTERPRETED TO MEAN THE EDITION INDICATED BY THE SUB-NUMBER LISTED ON THE COVER SHEET OR THE COPY INCLUDED IN THESE PLANS.
- 8. THE RESIDENT ENGINEER SHALL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE BITUMINOUS SURFACE COURSE.
- 9. CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED FROM THE ROADWAY DITCHES TO THE CHANNEL. ANY EXTRA REQUIRED GRADING SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 10. GRADING SHALL BE DONE BY HAND AROUND LIGHT POLES, UTILITY POLES, SIGN POSTS, SHRUBS, TREES OR OTHER NATURAL OR MAN-MADE OBJECTS WHERE SHALLOW FILLS OR CUTS ARE ADJACENT TO THE ITEMS. IT IS THE INTENT THAT THE LIMITS OF CONSTRUCTION BE SUCH AS TO PRESERVE IN THE ORIGINAL STATE AS MUCH AREA AS POSSIBLE. THE DECISION AS TO ITEMS TO REMAIN IN PLACE SHALL BE DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. THE REMOVAL OF EXISTING ENTRANCE CULVERTS SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
- 11. REMOVAL OF AGGREGATE MATERIAL AND OIL & CHIP BITUMINOUS MATERIAL SHALL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 12. SEEDING SHALL BE DONE ON ALL AREAS THAT ARE DISTURBED BY CONSTRUCTION OPERATIONS AS DIRECTED BY THE ENGINEER. SEEDING SHALL BE PAID FOR ONLY WITHIN THE PROPOSED RIGHT-OF-WAY OR EASEMENT LIMITS. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDED, AS DIRECTED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE. SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET OR IN AN UNTILLABLE CONDITION.
- 13. FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:


BITUMINOUS CONCRETE SURFACE COURSE
ALL AGGREGATE
BITUMINOUS MATERIALS (PRIME COAT)
AGGREGATE (PRIME COAT)
SEEDING FERTILIZER RATIO (NIT:PHOS:POT)
MULCH
TEMPORARY EROSION CONTROL SEEDING
112 LBS/SQ YD - IN
2.05 TONS/CU YD
6 LBS/SQ YD
6 LBS/SQ YD
90:90:90:90:90:18S/ACRE
100 LBS/ACRE

- 14. ACCESS TO ALL ENTRANCES SHALL BE MAINTAINED AT ALL TIMES.
- 15. ONLY THOSE TREES APPROVED FOR REMOVAL BY THE ENGINEER SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES, PLANTS, AND WETLANDS FROM DAMAGE. ALL TREES AND STUMPS INDICATED ON THE PLANS FOR REMOVAL SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR.
- 16. WHERE SECTION OR SUB-SECTION STONES OR PROPERTY MARKERS ARE ENCOUNTERED THE ENGINEER SHALL BE NOTIFIED BEFORE STONES ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND PRESERVE ALL PROPERTY MARKERS UNTIL AN AUTHORIZED SURVEYOR HAS WITNESSED OR REFERENCED THEIR LOCATION.
- 17. ALL PIPE CULVERTS SHALL BE PRECOATED GALVANIZED CORRUGATED STEEL PIPE.
- 18. FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.


RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	0
FAS 766	04-00176-00-BR	MADISON	26	3

CONTRACT NO. 97296

EXISTING SECTIONS



PROPOSED SECTIONS



REMOVAL SCHEDULE

LOCATION	REMOVE EXISTING STRUCTURE (EACH) 50100100	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNITS) 20100110
STA 447+63.19 TO STA 448+36.86	1	
STA 447+50.00, 60.00' LT TO STA 448+50.00, 60.00' LT		72
STA 449+73.44, 35.87' RT TO STA 450+07.43, 36.21' RT		
TOTAL	1	72

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (ACRE)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (TON)
	25000200	25000400	25000400	25000600	25100120
STA 446+00 LT TO STA 447+82 LT	0.10	9.0	9.0	9.0	0.2
STA 446+00 RT TO STA 447+82 RT	0.10	9.0	9.0	9.0	0.2
STA 448+15 LT TO STA 450+00 LT	0.15	13.5	13.5	13.5	0.3
STA 448+15 RT TO STA 450+50 RT	0.15	13.5	13.5	13.5	0.3
TOTAL	0.5	45.0	45.0	45.0	1.0

 RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 766	04-00176-00-BR	MADISON	26	4

CONTRACT NO. 97296

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING (LB) 28000250	PERIMETER EROSION BARRIER (FOOT) 28000400	TEMPORARY DITCH CHECKS (EACH) 28000300	EROSION CONTROL BLANKET (SQ YD) 25100630
STA 446+00 LT TO STA 447+82 LT	10			
STA 446+00 RT TO STA 447+82 RT	10			·····
STA 446+00 LT TO STA 447+00 LT		100		
STA 446+00 RT TO STA 447+50 RT		150		
STA 448+15 LT TO STA 450+00 LT	15			
STA 448+50 RT TO STA 450+50 RT	15			
STA 448+30 LT TO STA 450+00 LT				170
STA 448+30 RT TO STA 449+74 RT		-		144
STA 448+50 LT			1	
STA 448+50 RT	:		1	
STA 449+50 LT			1	
STA 449+50 RT			1	·····
STA 450+00 RT TO STA 450+50 RT		50		
TOTAL	50	300	4	314

GUARDRAIL SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 6A (EACH) 63100087	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)	GUARD RAIL MARKERS TYPE A
	63100087	63100167	78201000	78200410
STA 446+57.75 LT TO STA 447+07.75 LT		1	1	
STA 447+07.75 LT TO STA 447+51.50 LT	1			1
STA 447+51.50 LT TO STA 448+40.50 LT				1
STA 448+40.50 LT TO STA 448+84.25 LT	1			1
STA 448+84.25 LT TO STA 449+34.25 LT		1	1	1
STA 446+57,75 RT TO STA 447+07.75 RT		1	1	1
STA 447+07.75 RT TO STA 447+51.50 RT	1			1
STA 447+51.50 RT TO STA 448+40.50 RT				1
STA 448+40.50 RT TO STA 448+84.25 RT	1			1
STA 448+84.25 RT TO STA 449+34.25 RT		1	1	
TOTAL	4	4	4	8

RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
FAS 766	04-00176-00-BR	MADISON	26	5

CONTRACT NO. 97296

RIPRAP SCHEDULE

LOCATION	STONE RIPRAP CLASS A4 (SQ YD) 28100107	FILTER FABRIC W/ RIPRAP (SQ YD) 28200200
STA 447+30 TO STA 448+39 (SUGAR FORK CREEK)	460	460
STA 448+10, 47' LT TO STA 448+40, 47' LT	47	47
STA 448+10, 45' RT TO STA 448+40, 45' RT	47	47
TOTAL	554	554

PIPE SCHEDULE


LOCATION	PIPE CULVERT CL C, TYPE 2, 24" (FOOT) 542C1069
STA 449+74, 38.7' RT TO STA 450+10, 38.0' RT	36
TOTAL	36

AGGREGATE SCHEDULE

LOCATION	AGGREGATE SURFACE COURSE TYPE A, 8" (TON) 40200100
FRUIT ROAD:	
STA 446+00.00 TO STA 447+50.25	185
STA 448+41.75 TO STA 450+00.00	195
TOTAL	380

TOTAL SHEET SHEETS NO. SECTION COUNTY CONTRACT NO. 97296 ROAD ROAD CLOSED CLOSED 500 FT AHEAD W20-3 W20-3

TRAFFIC CONTROL PLAN STRUCTURE & ROADWAY CONSTRUCTION STA 446+00 TO STA 450+00 (NOT TO SCALE) ROAD CLOSED AHEAD W20-3 ROAD ROAD CLOSED CLOSED AHEAD 500 FT W20-3 W20-3 FRUIT ROAD FRUIT ROAD TYPE III BARRICADES
WITH ROAD CLOSED
SIGNS R-11-2 4830 TYPE III BARRICADES WITH ROAD CLOSED SIGNS R-11-2 4830 CLOSED **AHEAD** NOTES: THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER 72 HOURS PRIOR TO CLOSURE.
 ALL TRAFFIC CONTROL DEVICES SHALL BE REFLECTIVE AND INCLUDE LOW INTENSITY FLASHING LIGHTS.
 LOCATION OF TRAFFIC CONTROL DEVICES SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT.
 THE CONTRACTOR SHALL MAINTAIN TEMPORARY ACCESS TO DRIVEWAYS AFFECTED BY CONSTRUCTION.
 FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.
 TRAFFIC CONTROL SHALL CONFORM TO IDOT HIGHWAY STANDARDS: 702001-06, B.L.R. 21-6




B.M. On S.E. Headwall Comer of Existing Structure Elev 525.51

Existing Structure - S.N. 060-3045, Built in 1954, 4 Panels @ 70'-0" c. to c. end bearings, 20'-0" o. to o. width, Pratt Pony Truss - Riveted

COUNTY TOTAL SHEET NO. SECTION FAS 766 04-00176-00-BR

CONTRACT NO. 97296

Salvage - None



24' - (1" 40' - 0" 24' - 6" E Bent Sta. 447+51.50 Sta. 448+40.50 Sta. 448+16 P.G. Elev. 527.05 T.C.E. 525.34 P.G. Elev. 526.61 T.C.E. 524.89 P.G. Elev. 526.73 T.C.E. 525.02 Boring No. B-2 —€ Roadway & Profile Grade Line **E** Bent Sta. 447+76 P.G. Elev. 526.93 T.C.E. 525.22 T.C.E. *Top of Cop € Pilos € Plles-Boring No. B-1 Elev. Boring No. B-4 -

GENERAL NOTES


- The steel H-Piles shall be according to AASHTO M270 Grade 50.
 The Test Pile(s) shall be driven to 110 percent of the nominal
- required bearing indicated in the pile data information.

 3. See Special Provisions for boring logs.

TOTAL BILL OF MATERIAL

ltem	Unit	Super	Sub.		7-4-7
nem		Super	Piers	Abuts.	Total
Removal of Existing Structures	Each	1		2	1
Hot Mix Asphalt	Ton	56 .			56
Waterproofing Membrane System	Sq. Yd.	330.1			330.1
Concrete Structures	Cu. Yd.		20.4	22	42.4
Precast Prestressed Concrete Deck Beams (17" Depth)	Sq. Ft.	2970			2970
Steel Railing, Type SM	Foot	180			180
Reinforcement Bars	Pound		2460	2860	5320
Furnishing Steel Piles HP 10x42	Foot	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	558	682	1240
Driving Piles	Foot		558	682	1240
Test Piles Steel HP 10x42	Each		1	1	2
Name Plates	Each			1	1
Concrete Encasement	Cu. Yd.	***************************************	14.3	4.2	18.5
Portland Cement Mortar Fairing Course	Foot	900			900

PLAN



VIEW A-A PILE STUDS DETAIL

Provide 34" ogranular or solid flux filled headed study conforming to article 1006.32 of the standard specifications automatically end welded to piling. Cost shall be incidental to the cost of furnishing piles.

DESIGN SPECIFICATIONS 2002 AASHTO Standard Specifications - 17th ed.

LOADING HS20-44

Allow 25#/sq. ft. for future wearing surface.

SEISMIC DATA

Seismic Performance Category (SPC) = A Bedrock Acceleration Coefficient (A) = 0.09 Site Coefficient (S) = 1.5.

PILE DATA (2-PIERS)

Pile Type & Size: HP 10 x 42 Nominal Required Bearing: 135 Tons Allowable Resistance Available: 45 Tons Estimated Pile Length: 62 Feet Number of Production Piles: 9 Number of Test Piles: 1


PILE DATA (2-ABUTS.)

Pile Type & Size: HP 10 x 42 Nominal Required Bearing: 75 Tons Allowable Resistance Available: 25 Tons Estimated Pile Length: 62 Feet Number of Production Piles: 11 Number of Test Piles: 1

STATION 447+96 SUGAR FORK CREEK SEC. 04-00176-00-BR BUILT 2007 ROAD DIST. 08 MADISON COUNTY LOADING HS20 STR. NO. 060-3343

LETTERING FOR NAME PLATE

Locate Name Plate at SouthWest Corner of Bridge (See Std. CN)



WATERWAY INFORMATION

Drainage Are	a = 9.35	Sq Mi	Low G	rode Ele	v. = 512	.50 0	Sta. 4	47+96	
Flood	Freq.	. 0	Opening	Sq. F1.	Nat.	Head	- Ft.	Headwa	iter El.
1 1000	Yr.	C.F.S.	Exist.	Prop.	H.W.E.	Exist.	Prop.	Exist.	Prop.
Design	20	1922	441	431	523.12			523.42	523.12
Bose	100	2828	481	490	523.95	0.49	0.49	524.39	523.95
Overtopping			<u> </u>					1	
Max. Calc.	500	3697		560					

INDEX OF SHEETS

- General Plan & Elevation
- Standard CS-3317-25
- Standard CS-3317-40
- Standard CB-3317-36
- Standard CA-3317-10
- Standard CP-3317-10
- Standard CR-TSM
- 8. Standard CN
- 9. Standard CX-1

GENERAL PLAN & ELEVATION

ROUTE _


OVER SUGAR FORK CREEK


SECTION _04-00176-00-BR


MADISON COUNTY

STATION 447+96

GP-3 (04-04-05)







APPROVED APRIL 4. 2005


Engineer of Bridges and Structures

The std. reinf. and dimensions

shown on the 25' span cross


section is typical for all spans.

except as shown.




END BLOCK DETAILS

Each beam shall have four Lifting Loops, two at each end of beam cast in locations shown above. Loops shall be burned off after beams have been erected.



LIFTING LOOP DETAIL

Lifting loops shall be 2, ${}^{1}_{2}$ "6-270 ksi strands, as shown. Alternate approved lifting devices are also acceptable.




SECTION

CONTRACT NO. 97296

COUNTY

SHEETS



(RIGHT ANGLE)

DIMENSION 'C'

Skew Angle 'D'	0°	5°	ю°	<i>15</i> °	20°	25°	30°
Dimension 'C' (Inches)	0	31/8	6-8	958	13%	1634	2034


* TRANSVERSE STRAND PLACEMENT GUIDELINES

ifting.

Loops

- . Place strands symmetrically about centerline of beam.
- The minimum distance from center to center of strands in all directions shall be 2".
- 3. The minimum clearance from strand to dowel hole shall be '2".
- 4. The minimum clearance from strand to void shall be 1'2",

Vertical placement of strands shall not be adjusted to satisfy the above guidelines.



MIN. BAR LAP

#5 bars = 1'-8"

NOTES

- Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270.
- The nominal diameter shall be '2" and the nominal cross-sectional area shall be 0.153 square inches.
- 3. Reinforcement bars shall conform to the requirements of AASHTO M-31 or M-322. Grade 60.
- 4. Rail Post anchor devices shall be cast into outside beam as elsewhere specified.
- 5. When a Waterproofing Membrane System is specified, the top surface of the beams shall be screeded with a straightedge and finished with a hand float. The finished surface shall be free of depressions or high spots with sharp corners and the top edge of keys shall be rounded or chamfered a minimum of \(\frac{1}{4}\top{\chi}\).
- 6. Keyway surfaces shall be cleaned to remove form oil or other bond breaking material prior to shipment of the beams. Cleaning shall be done by sandblasting the keyway areas between the top of the beam and the bottom edge of the key.

DESIGN STRESSES

f' = 5,000 p.s.i.

 $f'_{cl} = 4.000 \text{ p.s.i.}$

 $f_s' = 270,000 \text{ p.s.l. } (l_2'' \neq Strand)$

f_{sl} = 201,960 p.s.l. (½" # Strand)

 $f_y = 60.000 \text{ p.s.i.}$


P.P.C. DECK BEAM DETAILS

33' ROADWAY


17" x 36" BEAMS

STANDARD CB-3317-36


III-19




IV-46



CONTRACT NO. 97296







DIMENSION 'E'

ELEVATION

	ъ	′=0°	D'	′=5°	'D'=10°	
GRADE	UPGRADE END	DOWNGR'ADE END	UPGRADE END	DOWNGRADE END	UPGRADE END	DOWNGRADE END
0%	278"	278"	278"	278"	278"	278"
Over 0% to 1%	2'8"	218"	218"	3"	234"	3"
Over 1% to 2%	278"	276"	2 ⁵ 8"	3'8"	238"	338"
Over 2% to 3%	278"	278"	2'2"	338"	218"	334"
Over 3% to 4%	278"	27."	23,"	35"	13,"	4"

Illinais Department of Transportation

PASSED APRIL 4, 2005
Thomas Normanulari
Engliser of Edgise Design
APPROVED APRIL 4, 2005

Engineer of Bridges and Structures


SPAN	TONS
25'	32
30'	37
35'	41
40'	45

MAXIMUM PILE LOADS

Longer of Either Span Supported by Pier.


DESIGN STRESSES

f'c = 3,500 psi fy = 60,000 psi



2'-8"0.-0.

BAR SI



NOTE

Reinforcement bars shall conform to the requirements of A.A.S.H.T.O. M-31 or M-322, Grade 60.


BILL OF MATERIAL FOR ONE PIER

Bar	No.	Size	Length	Shape	
Pi	9	#8	34'-5"		
s,	38	#4	10'-5"	ם	
u _I	8	#6	11'-7"		
Concrete	Structur	10.2 Cu. Yds.			
Reinforcement Bars			1230 Lb.		

P.P.C. DECK BEAMS PILE BENT PIER


33' RDWY. 17" BMS. 'D'=0". 5" OR 10"


STANDARD CP-3317-10



| RTE. | SECTION | COUNTY | TOTAL | SHEET | NO. | FAS 766 | 04-00176-00-BR | MADISON | 26 | 15

CONTRACT NO. 97296







Illinois Department of Transportation
PASSED APRIL 4, 2005

PASSED APRIL 4, 2005
Thomas Nomagalaki
Engineer of Africe Design
APPROVED APRIL 4, 2005
Ralph E. Andrean
Engineer of Bridges and Structures

NAME PLATE

STANDARD CN





DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

1 inch = 50 ft

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING, PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES. (EXCEPT AS DESCRIBED IN THE PLANS AND DIRECTED BY THE ENGINEER)

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

- 1. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- 2. TEMPORARY SEED ERODABLE BARE EARTH ON A WEEKLY BASIS TO MINIMIZE THE AMOUNT
- OF ERODABLE SURFACE AREA WITHIN THE CONTRACT LIMITS.
- 3. CONSTRUCT ROADSIDE DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- 4. CONTINUE BUILDING UP THE EMBANKMENT TO THE PROPOSED GRADE WHILE AT THE SAME

EXCAVATED AREAS AND EMBANKMENT SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT. THEY SHALL BE TEMPORARILY SEEDED IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANED FOR 7 DAYS.

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TOO CONTAIN ANY FUEL OR OTHER POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACITIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF $rac{1}{2}$ INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING THE WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE CONSTRUCTION FIELD ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT EROSION CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED FROM THE SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE WILL BE FOR ACCORDING TO ARTICLE

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

DESCRIPTION OF PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

ONCE PERMANENT EROSION CONTROL SYSTEMS, AS PROPOSED IN THE PLANS, ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER ACCEPTANCE BY MADISON COUNTY FINAL INSPECTION. MAINTENANCE UP TO THIS DATE WILL BE BY THE CONTRACTOR

STORM WATER POLLUTION PREVENTION PLAN (SWPPP):

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR TO THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE CONSTRUCTION SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONARI E AMOUNT OF TIME

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIME FRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THERFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN STANDARD 280001 OF THE PLANS. SECTION 280, TEMPORARY EROSION CONTROL, OF THE STANDARD SPECIFICATIONS ADDITIONALLY SUPLEMENTS THIS

SITE DESCRIPTION OF CONSTRUCTION ACTIVITY:

- THE PROJECT CONSISTS OF REPLACING AN EXISTING SINGLE SPAN PRATT PONY TRUSS BRIDGE WITH A 3-SPAN PRECAST PRESTRESSED CONCRETE DECK BEAM BRIDGE ON STEEL PILING AND CONCRETE SUB-STRUCTURE ON FRUIT ROAD APPROXIMATELY 3.0
- 2. CONSTRUCTION INCLUDES REPLACING THE EXISTING BRIDGE, EARTH EXCAVATION, EMBANKMENT, TREE REMOVAL, PIPE CULVERT,

DESCRIPTION OF INTENDED SEQUENCE FOR MAJOR CONSTRUCTION ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

- ESTABLISH EROSION CONTROLS AS NEEDED, INCLUDING, BUT NOT LIMITED TO, PERIMETER EROSION BARRIER, TEMPORARY DITCH
- ISOLATED TREE REMOVAL AS SHOWN ON THE SCHEDULE. TREES TO REMAIN WILL BE PROTECTED FROM DAMAGE.
 REMOVE EXISTING STRUCTURE, PERFORM CHANNEL EXCAVATION AND CONSTRUCT LOW-WATER CROSSING IF DESIRED.
 PERFORM EARTH EXCAVATION AND EMBANKMENT NECESSARY TO CONSTRUCT BRIDGE ABUTMENTS AND PIERS.
- PLACE RIPRAP UNDER BRIDGE AND PLACE DECK, FINISH BRIDGE.
 CONTINUE ROADWAY EMBANKMENT PLACEMENT AND FINAL GRADE EMBANKMENTS.
- INSTALL CULVERTS DURING EXCAVATION AND OTHER MISCELLANEOUS ITEMS.
- PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS RIPRAP DITCHES AND EROSION CONTROL BLANKET.
- PLACE AGGREGATE FOR ROADWAY AND PRIVATE ENTRANCES PERFORM FINAL SEEDING AND MULCHING.

AREA OF CONSTRUCTION SITE:

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.25 ACRES OF WHICH 1.05 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

OTHER REPORT STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE SWPP PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATIONS, SPECIAL PROVISIONS, PLAN DRAWINGS INDICATING DRAINAGE PATTERNS, AND SLOPES ANTICIPATED AFTER GRADING ACTIVITIES, WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

MISCELLANEOUS:

- TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRES. STRAW BALES, HAY BALES, PERIMETER EROSION BARRIER AND SILT FENCES WILL NOT BE PERMITTED FOR TEMPORARY OR PERMANENT DITCH CHECKS. DITCH CHECKS SHALL BE COMPOSED OF AGGREGATE, SILT PANELS, ROLLED EXCELSIOR, URETHANE FOAMIGEOTEXTILE (SILT WEDGES), AND/OR ANY OTHER MATERIAL APPROVED BY THE EROSION AND SEDIMENT CONTROL COORDINATOR.
- SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON THE SITE ON A REGULAR BASIS, AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE WILL BE PAID FOR ACCORDING TO ARTICLE 103.04. ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO THE APPROVAL AND USE OF THE PRODUCT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A
 NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED. FOR THIS APPLICATION ARE MET OR EXCEEDED, THE CONTRACTOR SHALL PROVIDE MANUFACTURER INSTALLATION PROCEDURES TO FACILITATE NEER IN CONSTRUCTION INSPECTION.
- ALL ITEMS SHALL BE CONSTRUCTED AS SHOWN ON STANDARD 280001 AND AS DIRECTED BY THE ENGINEER. MAINTENANCE AND CLEANING OF THE EROSION CONTROL ITEMS SHALL BE INCLUDED IN THE RESPECTIVE EROSION CONTROL PAY ITEM.
- 5. LAYOUT OF EROSION CONTROL MEASURES MAY BE ADJUSTED IN FIELD BY ENGINEER FOR VARING CONDITIONS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF:

ROADSIDE DITCHES AND SITE RUNOFF ARE CONTRIBUTED TO SUGAR FORK CREEK, A TRIBUTARY OF KASKASKIA RIVER.

EROSION AND SEDIMENT CONTROLS:

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE; TEMPORARY SEEDING, PERMANENT SEEDING MULCHING, PROTECTION OF TREES, PRESERVATION OF MATURE VEGETATION, AND OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 1 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

(a) AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.

(b) DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER, ALONG WITH REQUIRED

(c) AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, TEMPORARY DITCH CHECKS, INLET AND PIPE PROTECTION, AND PERIMETER EROSION BARRIER SHALL BE INSTALLED AS CALLED OUT IN THIS PLAN AND DIRECTED BY THE ENGINEER.

(d) BARE AND SPARSELY VEGETATED GROUND IN HIGH ERODABLE AREAS AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED AT NG OF CONSTRUCTION WHERE NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN DAYS. (e) IMMEDIATELY AFTER TREE REMOVAL IS COMPLETED AREAS WHICH ARE HIGHLY ERODABLE AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED WHEN NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN DAYS.

(f) AT LOCATIONS WHERE A SIGNIFICANT AMOUNT OF WATER DRAINS INTO THE CONSTRUCTION ZONE FROM OUTSIDE AREAS (ADJACENT LANDOWNERS), TEMPORARY DITCH CHECKS WILL BE UTILIZED TO LOCALLY DIVERT WATER, REDUCE FLOW RATES, AND COLLECT OUTSIDE

SILTATION INSIDE THE RIGHT-OF-WAY-LINE.

ESTABLISHMENT OF THESE TEMPORARY EROSION CONTROL MEASURES WILL HAVE ADDITIONAL BENEFITS TO THE PROJECT, DESIRABLE GRASS SEED WILL BECOME ESTABLISHED IN THESE AREAS AND WILL SPREAD SEEDS ON TO THE CONSTRUCTION SITE UNTIL PERMANEN

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBLITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS

Sand Street 1-23-07
COUNTY ENGINEER

