


EXISTING LOCATIONS FOR POLES TO BE RELOCATED

POLE NO.	EXISTING STATION OFFSET		
T2E3	114+42	77' LT	
T2F3	116+45	77' LT	
T2F5	107+83	75' LT	
T2E5	105+84	107' LT	

NOTES:

- NOTE 1: ALL LIGHTING EQUIPMENT SHOWN ON THIS DRAWING EXCEPT AS NOTED SHALL REMAIN IN PLACE AND OPERATIONAL DURING THE CONSTRUCTION STAGES OF THIS CONTRACT.
- NOTE 2: ALL LIGHTING EQUIPMENT SHOWN ON THIS DRAWING SHALL BE REMOVED AFTER THE PROPOSED LIGHTING IS INSTALLED AND MADE OPERATIONAL.
- NOTE 3: THIS EXISTING TEMPORARY LIGHT POLE SHALL BE RELOCATED TO THE NEW LOCATION, AND BE OPERATIONAL PRIOR TO COMMENCEMENT OF CONSTRUCTION STAGES. ALL NECESSARY CABLES AND EQUIPMENT NEEDED TO MAKE THE LIGHTING UNIT OPERATIONAL ARE INCIDENTAL TO PAY ITEM 84400125 "RELOCATE EXISTING TEMPORARY LIGHTING UNIT"



FILE NAME =	USER NAME = _GAI_	DESIGNED - PKG	REVISED -		EXISTING TEMPORARY LIGHTING PLAN	F.A.P. SECTION COUNTY TOTAL SHEET NO.
\$FILEL\$		DRAWN - MAA, SHM	REVISED -	STATE OF ILLINOIS	(SHEET 4 OF 5)	345 8R-R KANE 794 454
1	PLOT SCALE = 1"=50"	CHECKED - PKG	REVISED -	DEPARTMENT OF TRANSPORTATION	CONTRACT NO. 6	
	PLOT DATE = 12/8/2011	DATE - 12/16/11	REVISED -		SCALE: 1"= 50' SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST, NO. 1 ILLINOIS FED. AID PROJECT