PAY ITEM NUMBER	21101615	21101665	21101685	25000210	X2502014	X2502024	25100115	25100630	25200110	X0324097
PAY ITEM	TOPSOIL FURNISH	TOPSOIL FURNISH	TOPSOIL FURNISH	SEEDING, CLASS 2A	SEEDING, CLASS 4A	SEEDING, CLASS 4	MULCH, METHOD 2	EROSION CONTROL	SODDING, SALT	COARSE SAND
	AND PLACE, 4"	AND PLACE, 18"	AND PLACE, 24"		(MODIFIED)	(MODIFIED)		BLANKET	TOLERANT	PLACEMENT, 2"
Unit	SOYD	SOYD	SOYD	ACRE	ACRE	ACRE	ACRE	SOYD	SOYD	SQYD
SHEET										
LA-2 (top)	1935	0	127	0.5	0.0	0.0	0.0	1963	128	127
LA-2 (bottom)	9516	0	1953	1.4	0.6	0.0	0.6	7279	1529	1848
LA-3	30741	30595	3013	1.6	10.2	1.0	6.2	32214	2252	52635
LA-4	23583	8083	3312	1.0	5.8	0.0	3.6	15330	2585	13112
LA-5 (top)	10834	0	1677	1.4	0.9	0.0	0.7	7820	1317	1668
LA-5(bottom)	6610	0	813	0.7	0.8	0.0	0.4	5337	745	743
LA-6	13404	7357	774	0_8	3.6	0.0	3.2	5915	1047	16170
SUB-TOTAL	96623	46035	11669	7.3	22.1	1.1	14.7	75858	9603	86303
AT THE ENGINEER'S										
DISCRETION	4900	2400	600	0.7	2.2	0.1	1.5	7586	960	8630
GRAND TOTAL	101530	48440	12270	8.1	24.4	1.2	16.2	83450	10570	94940
	ı	ı	1							

SEE TOPSOIL NOTE BELOW

LANDSCAPING SCHEDULE


PAY ITEM NUMBER	A2002916	A2005016	A2006516	A2006616	A2006716	K0013060	K0012990
PAY ITEM	TREE, CELTIS OCCIDENTALIS	TREE, GYMNOCLADUS DIOICUS	TREE, QUERCUS BICOLOR	TREE, QUERCUS IMBRICARIA	TREE, QUERCUS MACROCARPA	PERENNIAL PLANTS, SEDGE	PERENNIAL PLANTS,
	(COMMON HACKBERRY), 2" CALIPER,	(KENTUCKY COFFEETREE), 2"	(SWAMP WHITE OAK), 2" CALIPER,	(SHINGLE OAK), 2" CALIPER,	(BUR OAK), 2" CALIPER,	MEADOW TYPE, 2" DIAMETER	ORNAMENTAL TYPE,
	BALLED AND BURLAPPED	CALIPER, BALLED AND BURLAPPED	BALLED AND BURLAPPED	BALLED AND BURLAPPED	BALLED AND BURLAPPED	BY 4" DEEP PLUG	GALLON POT
Unit	EACH	EACH	EACH	EACH	EACH	UNIT	UNIT
SHEET							
LA-2 (top)	0	0	0	0	0	0.00	0.00
LA-2 (bottom)	0	0	0	0	0	0.00	6.55
LA-3	0	7	3	0	5	0.00	10.86
LA-4	0	0	0	0	0	0.00	9.43
LA-5 (top)	0	0	0	0	0	0.00	4.87
LA-5(bottom)	0	0	0	0	0	0.64	0.69
LA-6	14	4	10	10	10	0.00	0.00
SUB-TOTAL	14	11	13	10	15	0.64	32,40
AT THE ENGINEER'S							
DISCRETION	0	0	0	0	0	0	0
GRAND TOTAL	14	11	13	10	15	0.64	32.40

LANDSCAPING NOTES


- 1. THE SEEDING DATES FOR BARE EARTH SEEDING OF MIXTURE CLASS 4A, 4B, 5A (MODIFIED), AND WETLAND MIX SHALL BE FROM NOVEMBER 15 TO MARCH 15. ALL SEEDING NOT SOWN ACCORDING TO THE SPECIFIED SEASONAL DATE SHALL REQUIRE PRIOR WRITTEN APPROVAL FROM THE ENGINEER. FAILURE TO SECURE SUCH APPROVAL SHALL RESULT IN THE REJECTION OF THE SEEDING AND REPLACEMENT BY THE CONTRACTOR AT HIS/HER EXPENSE.
- THE ENGINEER WILL CONTACT FABIOLA QUIROZ OF THE ROADSIDE DEVELOPMENT UNIT AT (847)705-4596, AT LEAST 7 DAYS PRIOR TO PLANTING FOR LAYOUT APPROVAL OF THE SEEDING, TREES, SHRUBS, VINES, PERENNIALS, AND PLUGS.

TOPSOIL NOTE

THE CONTRACTOR IS ADVISED THAT THE QUANTITY PROVIDED FOR THE VARIOUS "TOPSOIL FURNISH AND PLACE" ITEMS REPRESENTS THE TOTAL AMOUNT OF TOPSOIL REQUIRED FOR THE ENTIRE PROJECT. HOWEVER, THE CONTRACTOR SHALL RE-USE EXISTING TOPSOIL OBTAINED FROM STRIPPING OPERATIONS AS QUANTIFIED IN THE EARTHWORK SCHEDULE AS "TOPSOIL EXCAVATION AND PLACEMENT." THE QUANTITIES FOR THE VARIOUS "TOPSOIL FURNISH AND PLACE" ITEMS SHALL BE REDUCED BASED ON THE ACTUAL UTILIZATION OF THIS EXISTING TOPSOIL. NO ADJUSTMENT TO UNIT PRICES SHALL BE ALLOWED BASED ON THE REVISED QUANTITIES.



SCALE:



TREE PROTECTION VIA TEMPORARY FENCE
FOR TREE GROVE, FORESTED AREA, AND WETLANDS

AcDonough Associal ngineers / Architects

F3

ILE NAME =

0160122-SHT-LNDSCP01.dan

	USER NAME = YK1m	DESIGNED	-	JCL	REVISED -	
i		DRAWN	-	JCL	REVISED -	
	PLOT SCALE = 1:50	CHECKED	-	EJG	REVISED -	
	PLOT DATE = 10/14/2011	DATE	-	10/14/11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

	LANDOCARE COUE	DIEF AND	DETAULO		F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
LANDSCAPE SCHEDULE AND DETAILS					347	LY (HB & VB)	DUPAGE/KANE	421	131
						LA-1	CONTRACT	NO.	50122
NONE	SHEET NO. 1 OF 1 SH	HEETS STA.		TO STA.	FED. ROA	AD DIST. NO. 1 ILLINOIS FED. AL	D PROJECT		