SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL) (EACH)	RELOCATE SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 2 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 3 (SPECIAL) (SQ FT)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY (FOOT)
NEB-WP-1106	356+57	REC. & CULT. -- SCHAUMBURG CONVENTION CENTER NEXT RIGHT	8.0	5.5	8.0	5.5					1				44.0	36			
SWB-TR-1107A	356+99	GUIDE -- WOODFIELD RD TO IL 58 GOLF RD 3/4 MILE	18.0	12.0	18.0	12.0			216.0						216.0			6	
SWB-TR-1107B	356+99	GUIDE -- I90 CHICAGO 1/4 MILE	17.0	12.0	17.0	12.0			204.0						204.0				
SWB-TR-1107C	356+99	GUIDE -- I90 ROCKFORD EXIT	16.0	12.0	16.0	12.0			192.0						192.0				
NEB-TR-1108A	362+24	GUIDE -- KIRCHOFF RD 1 MILE	15.5	10.0	15.5	10.0			155.0						155.0			6	
NEB-TR-1108B	362+24	GUIDE -- ALGONQUIN RD EXIT	21.0	10.0	21.0	10.0			210.0						210.0				
NEB-PM-1108C	362+24	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0			28.0						28.0				
NEB-WP-1109	363+78	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1110	366+02	W4-2R -- LANE ENDS	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1111	367+18	W4-3R -- ADDED LANE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1112	369+94	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1113	372+42	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-PM-1114	373+11	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-TR-1115A	377+29	GUIDE -- I90 ROCKFORD 1/4 MILE	13.0	12.0	13.0	12.0			156.0						156.0			5	
SWB-TR-1115B	377+29	GUIDE -- ALGONQUIN RD EXIT	21.0	12.0	21.0	12.0			252.0						252.0				
NEB-PM-1116	381+65	W4-1R -- MERGE	4.0	4.0	4.0	4.0		16.0						16.0					
SWB-TR-1117A	385+93	GUIDE -- I90 ROCKFORD CHICAGO 1/2 MILE	13.0	13.0	13.0	13.0			169.0						169.0			4	
SWB-TR-1117B	385+93	GUIDE -- ALGONQUIN RD 1/4 MILE	18.5	13.0	18.5	13.0			240.5						240.5				
SWB-WP-1118	387+83	W12-1 -- DOUBLE ARROW	3.0	3.0	3.0	3.0					1		9.0			36			
NEB-WP-1119	393+47	REGULATORY -- MOVE OVER SLOW DOWN	13.5	6.5	-	-					1								
SWB-PM-1120A	396+03	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5	4.5						4.5						
SWB-PM-1120B	396+03	M1-I100 -- IL 53	3.0	3.0	3.0	3.0	9.0						9.0						
SWB-TR-1121A	397+49	GUIDE -- 290 EAST CHICAGO	27.5	13.0	27.5	13.0			357.5						357.5			6	
SWB-TR-1121B	397+49	GUIDE -- 90 ROCKFORD CHICAGO	17.0	13.0	17.0	13.0			221.0						221.0				
NEB-WP-1122A	397+79	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
NEB-WP-1122B	397+79	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
SWB-WP-1123	400+09	REC. & CULT. -- SCHAUMBURG CONVENTION CENTER NEXT RIGHT	8.0	5.5	8.0	5.5					1				44.0	36			
NEB-TR-1124A	402+12	GUIDE -- EUCLID AVE 3/4 MILE	14.5	10.0	14.5	10.0			145.0						145.0			5	
NEB-TR-1124B	402+12	GUIDE -- KIRCHOFF RD 1/4 MILE EXIT ONLY	15.0	10.0	15.0	10.0			150.0						150.0				
NEB-PM-1124C	402+12	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
NEB-PM-1124D	402+12	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-CL-1125	407+00	GUIDE -- ALGONQUIN RD HIGGINS RD WOODFIELD RD RIGHT LANES	24.0	15.0	24.0	15.0			360.0						360.0			3	
SWB-GM-1126	410+74	REGULATORY -- EXPRESS LANES EXIT TO HIGGINS RD PROHIBITED	13.5	8.5	-	-			114.8										
SWB-TR-1127A	414+89	GUIDE -- 290 EAST CHICAGO LEFT LANES	27.5	13.0	27.5	13.0			357.5						357.5			6	
SWB-TR-1127B	414+89	GUIDE -- 90 ROCKFORD CHICAGO RIGHT LANES	13.0	13.0	13.0	13.0			169.0						169.0				
SWB-PM-1127C	414+89	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
NEB-TR-1128A	417+60	GUIDE -- EAST EUCLID AVE 1/2 MILE	14.5	10.0	14.5	10.0			145.0						145.0			5	
NEB-TR-1128B	417+60	GUIDE -- KIRCHOFF RD EXIT ONLY	15.5	10.0	15.5	10.0			155.0						155.0				
NEB-PM-1128C	417+60	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
NEB-WP-1129	425+96	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	18			
SWB-WP-1130	428+29	W4-3R -- ADDED LANE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1131	430+86	REC. & CULT. -- ARLINGTON PARK RACECOURSE NEXT RIGHT	9.5	4.5	9.5	4.5			42.8						42.8	36			
SWB-WP-1132	434+91	D3-1 -- KIRCHOFF RD	7.5	1.5	7.5	1.5					1			11.3		36			
NEB-WP-1133	435+41	GUIDE -- THIRD DISTRICT COURT NEXT RIGHT	8.5	4.5	8.5	4.5					1				38.3	36			
SWB-WP-1134A	435+57	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
SWB-WP-1134B	435+57	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
SWB-CL-1135	436+86	GUIDE -- ALGONQUIN RD HIGGINS RD WOODFIELD RD RIGHT 3/4 MILE	24.0	15.0	24.0	15.0			360.0						360.0			3	
NEB-TR-1136A	441+08	GUIDE -- NORTHWEST HWY 1 1/2 MILE	20.0	12.0	20.0	12.0			240.0						240.0			8	
NEB-TR-1136B	441+08	GUIDE -- WEST EUCLID AVE 1/4 MILE	14.5	12.0	14.5	12.0			174.0						174.0				
NEB-TR-1136C	441+08	GUIDE -- EAST EUCLID AVE EXIT	18.0	12.0	18.0	12.0			216.0						216.0				
NEB-PM-1136D	441+08	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-WP-1137	441+77	GUIDE -- SHARE THE DRIVE	10.0	5.0	10.0	5.0					1				50.0	36			
NEB-WP-1138	445+56	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-WP-1139	447+27	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1140	450+67	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1141	452+21	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1142	452+67	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0					1				28.0	18			
NEB-BR-1143	454+79	GUIDE -- WEST EUCLID AVE EXIT	18.0	6.5	18.0	6.5			117.0						117.0			2	20
SWB-BR-1144	455+58	GUIDE -- EAST EUCLID AVE EXIT	18.0	6.5	18.0	6.5			117.0						117.0			2	20
SWB-WP-1145	458+34	W4-1R -- MERGE	4.0	5.0	4.0	5.0					1			20.0		18			

•F.A.I. 290 (INTERSTATE 290)
•F.A.U. 342 (IL ROUTE 53)

COPYRIGHT 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001211 - EXPIRES 4/30/2013
23lukb 4/23/03 PW 7/20/2012 \corp.baxwood.com\projects\CrystalLake\IDOT\60053-\40-Design\WO-27 IL-53 Signing\CADD-SURVEY\DRAWINGS\DGNS\60053-WO-27-SIGN-SCHDLE.dgn
...\Standards\Motorv\pdf-EDIT.plt
...\PLOTS\60053-WO-27-B&W.tbl

BAXTER & WOODMAN Consulting Engineers

USER NAME = 23lukb	DESIGNED - DJS	REVISED -
	DRAWN - UKB	REVISED -
PLOT SCALE = 1.0000 ' / in.	CHECKED - RWL	REVISED -
PLOT DATE = 3/7/2012	DATE - 12-13-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	2011-024-SG	DuPAGE/COOK	132	6
		CONTRACT NO. 60P24		

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT