SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL) (EACH)	RELOCATE SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 2 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 3 (SPECIAL) (SQ FT)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY (FOOT)
NEB-PM-1146	458+90	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0					1				28.0				
NEB-WP-1147	460+16	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-WP-1148	464+26	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1149	465+27	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-TR-1150A	469+05	GUIDE -- I90 ROCKFORD CHICAGO RIGHT 1 1/2 MILES	13.0	13.0	13.0	13.0			169.0						169.0			8	
SWB-TR-1150B	469+05	GUIDE -- EAST EUCLID AVE 1/4 MILE	14.5	13.0	14.5	13.0			188.5						188.5				
SWB-TR-1150C	469+05	GUIDE -- WEST EUCLID AVE EXIT	18.0	13.0	18.0	13.0			234.0						234.0				
SWB-PM-1151	469+18	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-WP-1152	474+83	GUIDE -- THIRD DISTRICT COURT SECOND RIGHT	8.5	4.5	8.5	4.5					1				38.3	36			
NEB-WP-1153A	475+30	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
NEB-WP-1153B	475+30	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
SWB-WP-1154	480+02	REC. & CULT. -- ARLINGTON PARK RACECOURSE SECOND RIGHT	9.5	4.5	9.5	4.5			42.8						42.8	36			
NEB-WP-1155	482+08	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
NEB-CL-1156	490+91	GUIDE -- NORTHWEST HWY 1/2 MILE	-	-	20.0	12.0									240.0				
SWB-WP-1158	496+00	R2-1 -- 55 MPH	-	-	4.0	5.0								20.0		18			
NEB-WP-1159	496+09	REC. & CULT. -- METROPOLIS TWIN LAKES NEXT RIGHT	9.5	6.0	9.5	6.0					1				57.0	54			
NEB-GM-1160	501+00	SERVICE -- PARK & RIDE NEXT RIGHT	-	-	10.5	7.0									73.5				
SWB-TR-1161A	501+70	GUIDE -- I90 ROCKFORD CHICAGO RIGHT 2 MILES	12.5	13.0	12.5	13.0			162.5						162.5			5	
SWB-TR-1161B	501+70	GUIDE -- WEST EUCLID AVE 1/2 MILE	14.5	13.0	14.5	13.0			188.5						188.5				
SWB-PM-1161C	501+70	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5	4.5						4.5						
SWB-PM-1161D	501+70	M1-I100 -- IL 53	3.0	3.0	3.0	3.0	9.0						9.0						
NEB-PM-1162	516+41	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0			28.0						28.0				
NEB-TR-1163A	514+04	GUIDE -- PALATINE RD 3/4 MILE	16.0	10.0	16.0	10.0			160.0						160.0			6	
NEB-TR-1163B	514+04	GUIDE -- NORTHWEST HWY EXIT	23.0	10.0	23.0	10.0			230.0						230.0				
SWB-WP-1164	516+62	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1165	518+70	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-WP-1166	523+18	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1167	525+65	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-TR-1168A	527+92	GUIDE -- EUCLID AVE 1 MILE	14.5	10.0	14.5	10.0			145.0						145.0			6	
SWB-TR-1168B	527+92	GUIDE -- NORTHWEST HWY EXIT	23.0	10.0	23.0	10.0			230.0						230.0				
SWB-TR-1168C	527+92	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-GM-1169	535+71	SERVICE -- PARK & RIDE NEXT RIGHT	10.5	7.0	10.5	7.0					1				73.5				
NEB-WP-1170A	538+01	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
NEB-WP-1170B	538+01	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
NEB-CL-1171	540+84	GUIDE -- EAST PALATINE RD 1/4 MILE	16.0	8.5	16.0	8.5			136.0						136.0			3	
SWB-CL-1172	541+83	GUIDE -- NORTHWEST HWY 1/4 MILE	-	-	20.0	12.0									240.0				
NEB-WP-1173	543+19	R2-1 -- 55 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
SWB-WP-1174A	545+93	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
SWB-WP-1174B	545+93	M1-I100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
NEB-TR-1175A	555+33	GUIDE -- WEST PALATINE RD 1/4 MILE	16.0	12.0	16.0	12.0			192.0						192.0			5	
NEB-TR-1175B	555+33	GUIDE -- EAST PALATINE RD EXIT	19.0	12.0	19.0	12.0			228.0						228.0				
NEB-PM-1176	556+51	W13-3 -- 25 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-WP-1177	557+00	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1178	560+78	REC. & CULT. -- METROPOLIS TWIN LAKES NEXT RIGHT	9.5	6.0	9.5	6.0					1				57.0	54			
NEB-WP-1179	561+33	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-WP-1180	563+87	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1181	565+91	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-CL-1182	566+06	GUIDE -- EAST PALATINE RD EXIT	19.0	8.0	19.0	8.0			152.0						152.0			4	
SWB-WP-1183	566+50	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0					1				28.0	18			
NEB-CL-1184	571+77	GUIDE -- WEST PALATINE RD EXIT	19.0	8.0	19.0	8.0			152.0						152.0			4	
NEB-WP-1185	572+40	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0					1				28.0	18			
SWB-WP-1186	572+66	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
NEB-WP-1187	573+30	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
NEB-WP-1188	577+04	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
SWB-WP-1189	577+31	E5-1 -- EXIT	6.0	5.0	6.0	5.0					1				30.0	36			
SWB-PM-1190	580+53	W13-3 -- 30 MPH	4.0	5.0	4.0	5.0		20.0						20.0					
SWB-TR-1191A	582+68	GUIDE -- NORTHWEST HWY 1 MILE	20.0	12.0	20.0	12.0			240.0						240.0			9	
SWB-TR-1191B	582+68	GUIDE -- EAST PALATINE RD 1/4 MILE	16.0	12.0	16.0	12.0			192.0						192.0				
SWB-TR-1191C	582+68	GUIDE -- WEST PALATINE RD EXIT	19.0	12.0	19.0	12.0			228.0						228.0				
NEB-WP-1192A	589+03	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			

•F.A.I. 290 (INTERSTATE 290)
•F.A.U. 342 (IL ROUTE 53)

COPYRIGHT 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001211 - EXPIRES 4/30/2013
23Lukb 4/23/07 PW 7/20/2011 corp.baxwood.com\projects\CrystalLake\IDOT\60053-\40-Design\WO-27 IL-53 Signing\CADD-SURVEY\DRAWINGS\DGNS\60053-WO-27-SIGN-SCHDLE.dgn ...\Standards\plotdrv\pdf-EDIT.plt ...\PLOTS\60053-WO-27-B&W.tbl

BAXTER & WOODMAN Consulting Engineers

USER NAME = 23lukb	DESIGNED - DJS	REVISED -	
	DRAWN - UKB	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - RWL	REVISED -	
PLOT DATE = 3/7/2012	DATE - 12-13-11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	2011-024-SG	DuPAGE/COOK	132	7
		CONTRACT NO. 60P24		

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT