

SUMMARY OF QUANTITIES				URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	0005							
45100100	CRACK ROUTING (PAVEMENT)	FOOT	336050	336050						
45100200	CRACK FILLING	POUND	127699	127699						
67100100	MOBILIZATION	L SUM	1	1						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	690	690						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
* X7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	132089	132089						
* X7800825	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 5 INCH	FOOT	17592	17592						
* X7800835	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 6 INCH	FOOT	2293	2293						
* X7800845	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH	FOOT	6949	6949						
* X7800855	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 12 INCH	FOOT	856	856						
* X7800870	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 24 INCH	FOOT	240	240						
* X7800800	HOT SPRAY THERMOPLASTIC PAVEMENT LETTERS AND SYMBOLS	SQ FT	618.8	618.8						

**Specialty Items*

FILE NAME = c:\pwwork\windat\windat\d0291571\012371	USER NAME = windat	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CRACK & JOINT SEALING - IL 394 SUMMARY OF QUANTITIES	F.A. RTE. 332	SECTION 2011-225-1	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3
RIGHT-PLAN-Design.dgn	DRAWN -	REVISED -	SCALE: SHEET OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -								
PLOT DATE = 2/17/2012	DATE -	REVISED -								