

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	112R-N	MCHEMRY	266	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62537				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				ROADWAY	TRAFFIC SIGNALS RTE 31 @ RTE 176	RTE 31/RTE 176 PRE-EMPTION EQUIPMENT	TRAFFIC SIGNAL INTERCONNECT	UTILITIES
				20% STATE 0003	20% STATE 0021	100% CRYSTAL LAKE 0021	80% FED 20% STATE 0021	100% CRYSTAL LAKE 0043
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,057	1,057				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	829	829				
40702700	FURNISH PROFILOGRAPH	L SUM	1	1				
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4 (JOINTED)	SQ YD	47,437	47,437				
42001300	PROTECTIVE COAT	SQ YD	57,824	57,824				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	514	514				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6,129	6,129				
44000100	PAVEMENT REMOVAL	SQ YD	45,096	45,096				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	6,150	6,150				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	14,586	14,586				
44000300	CURB REMOVAL	FOOT	1,009	1,009				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,187	12,187				
44000600	SIDEWALK REMOVAL	SQ FT	5,737	5,737				
44004000	PAVED DITCH REMOVAL	FOOT	269	269				
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,935	3,935				
44201690	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	44	44				
44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	67	67				
44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	67	67				
44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	44	44				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	22	22				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	305	305				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	65	65				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	115	115				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	236	236				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,902	2,902				
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2				
50105220	PIPE CULVERT REMOVAL	FOOT	2,215	2,215				
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2				
54010402	PRECAST CONCRETE BOX CULVERTS, 4' X 2'	FOOT	75	75				
54200217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	159	159				
54200220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	55	55				
5421D012	PIPE CULVERTS, CLASS D, TYPE 1, 12" (TEMPORARY)	FOOT	346	346				
5421D015	PIPE CULVERTS, CLASS D, TYPE 1, 15" (TEMPORARY)	FOOT	226	226				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	3	3				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3				
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE, 24"	EACH	1	1				
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	3	3				
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	3	3				

PLAN

DATE _____

BY _____

REVISIONS

PLOTTED _____

CHECKED _____

DATE _____

NOTE BOOK NO. _____

FILE NAME _____

PROFILE

DATE _____

BY _____

REVISIONS

PLOTTED _____

CHECKED _____

DATE _____

NOTE BOOK NO. _____

FILE NAME _____

⊕ - DENOTES SPECIALTY ITEMS
 △ - 0042 COST CODE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 336
 IL RTE 31 AND IL RTE 176

SUMMARY OF QUANTITIES

SCALE: NTS
 DATE: 02/10/2012

DRAWN BY: BCD
 CHECKED BY: BDH