





- BASED ON CONTROLLER CABINET TYPE IV WITH BASE DIMENSIONS OF 26" x 44" (660mm x 1118mm).
   ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
- 2. BASED ON UNINTERRUPTIBLE POWER SUPPLY CABINET WITH BASE DIMENSIONS OF 16" x 25" (406mm x 635mm). ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
- 3. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV.
- 4. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV AND UNINTERRUPTIBLE POWER SUPPLY CABINET.
- 5. DRILLED HOLES THROUGH THE PLATFORM BASE TO MATCH THE CONTROLLER CABINET BOLT TEMPLATE, FASTEN THE CONTROLLER CABINET TO THE PLATFORM WITH CARRIAGE BOLTS, WASHERS AND NUTS.
- 6. FASTEN ALL SUPPORT WOOD FRAMING TO THE WOOD POSTS WITH 2 LAG SCREWS FOR EACH CONNECTION.

## TEMPORARY SIGNAL CONTROLLER WOOD SUPPORT PLATFORM

CABLE SLACK LENGTH	FEET	METER		
HANDHOLE	6.5	2.0		
DOUBLE HANDHOLE	13.0	4.0		
SIGNAL POST	2.0	0.6		
MAST ARM	2.0	0.6		
CONTROLLER CABINET	1.5	0.5		
FIBER OPTIC AT CABINET	13.0	4.0		
ELECTRIC SERVICE AT (CABINET OR SERVICE LOCATION)	1.5	0.5		
GROUND CABLE (SIGNAL POST, MAST ARM, CABINET)	1.5	0.5		
GROUND CABLE (BETWEEN FRAME AND COVER)	5.0	1.6		

CABLE SLACK

VERTICAL CABLE LENGTH			
MAST ARM POLE ( MAST ARM MOUNTED SIGNAL HEAD)			
(L = MAST ARM LENGTH - DISTANCE TO SIGNAL HEAD FROM END OF ARM)	20.0+L	6.0+L	
BRACKET MOUNTED (MAST ARM POLE OR SIGNAL POLE)	13.0	4.0	
PEDESTRIAN PUSH BUTTON	6.0	2.0	
SERVICE INSTALLATION POLE MOUNT TO SERVICE DROP	13.5	4.1	
SERVICE INSTALLATION POLE MOUNT TO GROUND	13.5	4.1	
SERVICE INSTALLATION GROUND MOUNT	6.0	2.0	
FOUNDATION (SIGNAL POST, MAST ARM POLE, CONTROLLER CABINET, SERVICE-GROUND MOUNT)	3.0	1.0	

VERTICAL CABLE LENGTH

DEPTH OF FOUNDATION

FOUNDATION	DEPTH			
TYPE A - Signal Post	4'-0" (1.2m)			
TYPE C - CONTROLLER W/ UPS	4'-0" (1.2m)			
TYPE D - CONTROLLER	4'-0" (1.2m)			
SERVICE INSTALLATION, GROUND MOUNT, TYPE A - SQUARE	4'-0" (1.2m)			

## NOTES:

- ① Foundation Foundation Diameter Quantity of Size of Rebars Spiral Mast Arm Length Diameter Less than 30' (9.1 m) 10'-0" (3.0 m) 30" (750mm) 24" (600mm) 6(19) Greater than or equal to 30' (9.1 m) and less than 40' (12.2 m) 30" (750mm) 24" (600mm) 6(19) 13'-6" (4.1 m) 11'-0" (3-4 m) 36" (900mm) 30" (750mm) 7(22) 12 Greater than or equal to 40' (12.2 m) and less than 50' (15.2 m) 7(22) 13'-0" (4.0 m) 36" (900mm) 30" (750mm) 12 Greater than or equal to 50' (15.2 m) and up to 55' (16.8 m) 15'-0" (4.6 m) 36" (900mm) 30" (750mm) 12 7(22) Greater than or equal to 56' (16.8 m) and less than 65' (19.8 m) 21'-0" (6.4 m) 42" (1060mm 36" (900mm) 16 8(25) Greater than or equal to 65' (19.8 m) and up to 25'-0" (7.6 m) 42" (1060mm) 36" (900mm) 8(25)
- These foundation depths are for sites which have cohesive soils (clayey slit, sandy clay, etc.) along
  the length of the shaft, with an average Unconfined Compressive Strength (Qu) > 1.0 tsf (100 kpa).
  This strength shall be verified by boring data prior to construction or with testing by the Engineer
  during foundation drilling. The Bureau of Bridges & structures should be contacted for a revised
  design if other conditions are encountered.
- 2. Combination mast arm assemblies under 55 feet (16.8 m) shall use  $36^{\prime\prime}$  (900 mm) diameter foundations.
- 3. Combination mast arm assemblies under 56 feet (16.8 m) through 75 feet (22.9 m) shall use 42" (1060 mr diameter foundations.
- 4. For mast arm assemblies with dual arms refer to state standard 878001.

## DEPTH OF MAST ARM FOUNDATIONS, TYPE E

FILE NAME =	USER NAME = ZACH WALLSTEN	DESIGNED - DAD	REVISED -		DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS  SCALE: NONE SHEET NO. 5 OF 6 SHEETS STA. TO STA.		SECTION	COUNTY	TOTAL S	HEET
4281.800-TR1.dwg		DRAWN - BCK	REVISED -	STATE OF ILLINOIS			09-00206-08-TL	DuPAGE	53	9
	PLOT SCALE = 1" = .0833'	CHECKED - DAD	REVISED -	DEPARTMENT OF TRANSPORTATION			TS-05	CONTRACT	#: 6362	5
1	PLOT DATE = 12/16/2011	DATE - 10-28-09	REVISED -				ILLINOIS FED. A	ID PROJECT		