## SCHEDULE OF QUANTITIES

ST. CHARLES ROAD AT SWIFT ROAD

			ST. CHARLES ROAD AT SWIFT ROAD
NO.	QUANT.	UNIT	
1.	12	CU YD	EARTH EXCAVATION
2.	305	SQ FT	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
3.	24	SQ FT	DETECTABLE WARNINGS
4.	50	FOOT	COMBINATION CURB AND GUTTER REMOVAL
5.	50	FOOT	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
6.	155	FOOT	THERMOPLASTIC PAVEMENT MARKING - LINE 6"
7.	1		SERVICE INSTALLATION - POLE MOUNTED
8.	1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
9.	1	EACH	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET
10.	1	EACH	TRANSCEIVER - FIBER OPTIC
11.			ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C
12.	429	FOOT	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C
13.			ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C
14.	47	FOOT	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C
15.	3	EACH	
16.	1		SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED
17.	1		SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED
18.	1		SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED
19.			SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED
20.	2		PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER
21.			TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM
22.	5	EACH	INDUCTIVE LOOP DETECTOR
23.	2		PEDESTRIAN PUSH-BUTTON
24.	1		RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT
25.	238	FOOT	REMOVE ELECTRIC CABLE FROM CONDUIT
26.	1		REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
27.	1	EACH	REMOVE EXISTING SERVICE INSTALLATION

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

I.D.O.T. TRAFFIC SIGNAL INSTALLATION TOTAL ELECTRICAL SERVICE REQUIREMENTS WATTAGE								
	WATTAGE							
TYPE	NO. LAMPS	INCAND.	L.E.D.	% OPERATION				
SIGNAL (RED)	10	135	17	0.50	85.0			
SIGNAL (YELLOW)	10	135	25	0.25	62.5			
SIGNAL (GREEN)	10	135	15	0.25	37.5			
ARROW	8	135	12	0.10	9.6			
PED. SIGNAL	2	90	25	1.00	50.0			
CONTROLLER	1	-	100	1.00	100.0			
LUMINAIRE	2	250	-	0.50	250.0			
L.E.D. ST. NAME SIGN	_	-	64	0.50	_			
VIDEO SYSTEM	-	-	150	1.00	www			
BATTERY BACKUP	_	-	25	1.00	_			
ILLUMINATED SIGN	-		25	0.05				
				TOTAL =	594.6			

ENERGY COSTS - BILLED TO: VILLAGE OF GLEN ELLYN
(ADDRESS) 20 S. LAMBERT ROAD
(ADDRESS) GLEN ELLYN, IL 60137
ENERGY SUPPLY - CONTACT: MS. DEB RANKIN
PHONE: (630) 691-4379
COMPANY: COM-FD

FILE NAME =


4281.800-TR1.dwg

USER NAME = ZACH WALLSTEN DESIGNED - JRD REVISED --DRAWN - ZCW REVISED -REVISED PLOT DATE = 12/16/2011 - 12/16/2011 REVISED -

PROPOSED INTERCONNECT TO RIFORD ROAD/ ACKERMAN PARK TRACER CABLE ST. CHARLES \$10<\m ROAD 

**SWIFT ROAD** 

## CABLE PLAN



EXISTING EMERGENCY VEHICLE PREEMPTORS						
EMERGENCY VEHICLE PREEMPTOR	3	4				
MOVEMENT		-				

EXISTING AND PROPOSED PHASE DESIGNATION DIAGRAM

STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, & EMERGENCY VEHICLE PREEMPTION SEQUENCE ST. CHARLES ROAD AT SWIFT ROAD SHEET NO. OF SHEETS STA.

 
 GHA
 #4281.800

 COUNTY
 TOTAL SHEET NO.

 DuPAGE
 53
 27
 SECTION 09-00206-08-TL CONTRACT #: 63625