



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| | | | | | | | | | | |
|--|----------------------------|---------------------|------------------------------|---|--|--|---------------------------|--------------------|--------------|-----------|
| FILE NAME = 11552-DTLS-04-BD22 - BD-22 | USER NAME = bauerd1 | DESIGNED -- R. SHAH | REVISED -- A. ABBAS 04-27-98 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT | F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | PLOT SCALE = 50.000' / IN. | CHECKED -- | REVISED -- R. BORO 01-01-07 | | | 1609 | 11-00111-00-RS | COOK | 16 | 13 |
| | PLOT DATE = 10/27/2008 | DRAWN -- | REVISED -- R. BORO 09-04-07 | | | BD400-04 (BD-22) | | CONTRACT NO. 63680 | | |
| | | CHECKED -- 10-25-94 | REVISED -- K. ENG 10-27-08 | | | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003 (919) | | | | |
| | | | | | | SCALE: | SHEET NO. 13 OF 16 SHEETS | STA. | TO STA. | |