

**SCHEDULE OF MATERIALS**

SIDEWALK SCHEDULE				
STA	O/S	SIDEWALK REMOVAL (SQ FT)	PCC SIDEWALK, 5 INCH (SPECIAL) (SQ FT)	DETECTABLE WARNINGS (SQ FT)
11+73	RT	80.0	80.0	20.0
11+78	LT		40.0	16.0
12+15	RT	88.0	55.0	10.0
18+02	LT		40.0	16.0
18+10	RT	103.0	103.0	20.0
18+48	RT	84.0	50.0	10.0
21+58	RT	138.0	83.0	10.0
21+91	LT		50.0	16.0
21+99	RT	125.0	125.0	20.0
26+80	RT	111.0	59.0	10.0
27+20	RT	28.0		
27+20	RT	64.0	64.0	10.0
29+25	LT		192.0	36.0
29+65	LT	109.0	66.0	10.0
34+28	LT		35.0	10.0
34+70	RT	29.0		
36+80	LT	119.0	119.0	20.0
36+80	RT	119.0	119.0	20.0
37+20	LT	119.0	119.0	20.0
37+20	RT	119.0	119.0	20.0
38+50	LT		40.0	16.0
38+50	RT		40.0	16.0
39+82	LT	63.0	40.0	10.0
40+20	LT	63.0	40.0	10.0
41+65	LT		162.5	72.0
ANDOVER DRIVE	LT	97.0	51.0	10.0
ANDOVER DRIVE	LT	53.0	53.0	20.0
43+72	RT	128.0	85.0	10.0
50+70	LT		100.0	16.0
51+07	LT		100.0	16.0
53+58	LT		60.0	16.0
53+87	LT		40.0	16.0
57+20	RT	57.0	38.0	10.0
57+57	RT	57.0	38.0	10.0
<b>TOTALS:</b>		1953.0	2405.5	542.0

DRIVEWAY SCHEDULE				
Station	o/s	Driveway Pavement Removal (SQ YD) (PCC DRIVES ONLY)	PCC Driveway Pavement, 6" (SQ YD)	HMA Driveway Surface R&R (SQ YD)
12+25	RT			9.3
13+12	RT	17.1	17.1	
13+42	RT			19.4
14+99	RT	11.7	11.7	
16+31	RT			9.3
18+74	RT			10.1
20+41	RT	19.4	19.4	
20+96	RT	10.9	10.9	
22+32	RT			9.7
23+03	RT	17.1	17.1	
23+65	RT			15.6
23+96	RT	15.6	15.6	
25+10	RT	9.3	9.3	
30+02	RT	11.7	11.7	
30+90	LT	10.1	10.1	
33+33	LT	15.6	15.6	
47+92	RT	10.1	10.1	
50+61	RT	9.3	9.3	
52+00	RT	10.9	10.9	
52+65	RT	10.9	10.9	
55+92	RT	10.9	10.9	
<b>TOTALS:</b>		190.6	190.6	73.4

INLETS TO BE ADJUSTED	
LOCATION	O/S
11+81	RT
16+13	RT
16+13	LT
20+06	RT
20+06	LT
29+31	LT
29+54	LT
29+70	LT
45+55	RT
55+90	RT
<b>TOTAL:</b>	10

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	
LOCATION	O/S
30+97	RT
37+12	RT
43+37	LT
<b>TOTAL:</b>	3

**SUMMARY OF QUANTITIES**

ITEM NO.	PAY ITEM	UNIT	CONSTRUCTION TYPE CODE
			0005
			TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	31
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	21
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7
40600300	AGGREGATE (PRIME COAT)	TON	34
40600400	MXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	683
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	127
40603335	HOT-MX ASPHALT SURFACE COURSE, MX "D", N50	TON	1,366
40800050	INCIDENTAL HOT-MX ASPHALT SURFACING	TON	7
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	192
42400800	DETECTABLE WARNINGS	SQ FT	542
44000158	HOT-MX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	16,245
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	192
44000600	SIDEWALK REMOVAL	SQ FT	1,953
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	378
48101200	AGGREGATE SHOULDERS, TYPE B	TON	62
60260100	INLETS TO BE ADJUSTED	EACH	10
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	73
63200310	GUARDRAIL REMOVAL	FOOT	25
67100100	MOBILIZATION	L SUM	1
# 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
# 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	606
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	101
72000100	SIGN PANEL - TYPE 1	SQ FT	40
72900100	METAL POST - TYPE A	FOOT	184
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	30
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	329
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,466
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	509
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	104
# X2020110	GRADING AND SHAPING SHOULDERS	UNIT	14
# X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	2,406
# X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3
# XX006947	HOT-MX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	74
# XX007278	PARKWAY RESTORATION	SQ YD	803
# Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,125
# Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52

# INDICATES ITEM COVERED BY SPECIAL PROVISION

\* INDICATES SPECIALTY ITEM

COPYRIGHT © 2012 BY BAXTER & WOODMAN, INC. ...  
 LICENSE NO. 184-00121-EXPRES 4/20/2013  
 56362r



DESIGNED - TMS	REVISED -
DRAWN - KAR	REVISED -
CHECKED - JJF	REVISED -
DATE - 12-05-11	FILE - 110805-S00.sht

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES AND SCHEDULE OF MATERIALS**

SCALE: NONE STA. TO STA.

F.A.U. RTE. 1682	SECTION 11-00053-00-RS	COUNTY COOK	TOTAL SHEETS 15	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 63691				