



- LEGEND**
- CONCRETE SIDEWALK REMOVAL
 - DRIVEWAY REMOVAL
 - HMA REMOVAL, SPECIAL
 - SEEDING, BLANKET AND NUTRIENTS
 - HOT MIX ASPHALT SURFACE REMOVE - BUTT JOINTS (10' UNLESS OTHERWISE INDICATED)
 - COMBINATION CURB AND GUTTER REMOVAL, SPECIAL AND COMBINATION CONCRETE CURB B-6.12, SPECIAL
 - COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT
 - BUFFALO ADJUSTMENT SPECIAL
 - CATCH BASIN TO BE FILLED TO MAINTAIN FLOW
 - CATCH BASIN TO BE REMOVED
 - CATCH BASIN TO BE REMOVED AND REPLACED WITH CB, TYPE C W/ TYPE 1 FRAME, OL
 - DRAINAGE STRUCTURE TO BE ADJUSTED WITH A NEW TYPE 1 FRAME, OPEN LID
 - DRAINAGE STRUCTURE TO BE ADJUSTED WITH A NEW TYPE 1 FRAME, CLOSED LID
 - DRAINAGE STRUCTURE TO BE ADJUSTED
 - FRAMES AND LID TO BE ADJUSTED, SPECIAL
 - CATCH BASIN TO BE RECONSTRUCTED WITH A NEW TYPE 1 FRAME, OPEN LID

PROPOSED CURB AND GUTTER GRADE INFORMATION

LOCATION	OFFSET	PROP. ELEVATION	INFORMATION
17+99.41	LT	586.32	DRAINAGE STRUCTURE
19+00	LT	586.72	SUMMIT
19+49.40	LT	586.52	DRAINAGE STRUCTURE
20+11.02	LT	586.29	SUMMIT
20+80.67	LT	586.46	SUMMIT
21+39.76	LT	586.12	DRAINAGE STRUCTURE
17+99.23	RT	586.33	DRAINAGE STRUCTURE
18+93.83	RT	586.71	SUMMIT
19+47.72	RT	586.26	DRAINAGE STRUCTURE
20+08.42	RT	586.47	SUMMIT
20+80.67	RT	586.29	SUMMIT
21+39.76	RT	586.04	DRAINAGE STRUCTURE

NOTES
1. LIMITS ON ALL SIDE STREETS SHALL BE TO RADIUS RETURNS.

FILE NAME = 11556-PLAN-01 - IDOT P01	USER NAME =	DESIGNED - RJW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIBLEY BOULEVARD RESURFACING TORRENCE AVENUE TO STATE-LINE ROAD PAVEMENT PLAN	F.A.U. RTE. 3787	SECTION 11-00151-00-RS	COUNTY COOK	TOTAL SHEETS 27	SHEET NO. 6	
	PLOT SCALE =	CHECKED - ER	REVISED -		SCALE: 1"=50'	SHEET NO. 6 OF 27 SHEETS	STA. 13+15 TO STA. 22+00		CONTRACT NO. 63693		
	PLOT DATE = 12-07-11	DRAWN - MED	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003 (907)						
		CHECKED - AG	REVISED -								