

> LAKE STREET - PROPOSED TYPICAL SECTION STA. 104+82 TO STA. 146+17

LEGEND

- 1 EXISTING P.C.C. PAVEMENT, 7"
- 2 EXISTING GRANULAR SUB-BASE
- (3) EXISTING MONOLITHIC 6" BARRIER CURB
- (4) PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH) (X4400100)
- 5) HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" (44000159)
- 6 COMBINATION CURB AND GUTTER REMOVAL (44000500)
 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (60604400)
 (AT LOCATIONS SHOWN ON PLANS AND AS DIRECTED BY THE ENGINEER)
- 7 SAW CUTS (44213200) (2 1/4" AT PCC SURFACE REMOVAL)
- 8 CLASS C PATCH, TYPE 1, 7 INCH (44201313) OR CLASS D PATCH, 9 INCH (44201749, 44201753, 44201757, 44201759) (SEE PLAN SHEETS FOR LOCATION AND TYPES)

- REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)
- 10 POROUS GRANULAR EMBANKMENT, SUBGRADE (Z0042002)
- #6 EPOXY COATED TIE BARS, 24" LONG @ 24" C-C, DRILLED & GROUTED IN PLACE INCLUDED IN THE COST OF COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18
- (12) 1" POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 (40600827)
- (13) 1 1/2" HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (40603335)
- (14) EXISTING SIDEWALK, 4"
- (15) PORTLAND CEMENT CONCRETE SIDEWALK, 4"



REMOVAL

NOTES:

LOCATIONS AND DEPTH OF REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL WILL BE DETERMINED BY THE ENGINEER AS FIELD CONDITIONS REQUIRE.

CONTRACTOR SHALL MILL HMA SURFACE BEFORE PATCHING.

AIR VOIDS
4% @ 50 GYR.
3.5% @ 50 GYR.
4% @ 50 GYR.
4% @ 50 GYR.

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SO YD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR "PERCENT OF RAP" SEE SPECIAL PROVISIONS.

FILE NAME =
\sheet\2253_sht_tupsed# dan
(allee c (2233 and dipage and din
CIVILTECH

 ETS TON EGGATION AND THEST									
USER NAME = eds	DESIGNED	-	EDS	REVISED	-				
	DRAWN		EDS	REVISED	w-				
PLOT SCALE = 1.00000 '/ in.	CHECKED	-	DNM	REVISED	-				
PLOT DATE = 2/20/2012	DATE	-	02/06/12	REVISED	-				

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS						F.A. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
						1236	08-00100-00-PV	LAKE	35	6
								CONTRACT	NO.	63697
SCALE: N.T.S.	SHEET NO. 1	OF 2	SHEETS	STA. 104+82	TO STA. 146+17	FED. RO	DAD DIST. NO. 7 ILLINOIS FED. A	ID PROJECT		