1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES - IL 251 AT N KINNIKINNICK CREEK
3 .	SUMMARY OF QUANTITIES - IL 251 AT N KINNIKINNICK CREEK
4	SCHEDULE OF QUANTITIES- IL 251 AT N KINNIKINNICK CREEK
5 - 7	TRAFFIC CONTROL AND PROTECTION PLAN - IL 251 AT N KINNIKINNICK BRIDGE STAGE!
8 - 10	TRAFFIC CONTROL AND PROTECTION PLAN - IL 251 AT N KINNIKINNICK BRIDGE STAGE II
11	APPROACH PAVEMENT SURFACE REMOVAL AND REPLACEMENT PLAN - IL 251 AT N. KINNIKINNICK CREEK
12	PAVEMENT MARKING PLAN - IL 251 AT N KINNIKINNICK BRIDGE
13	GENERAL PLAN AND ELEVATION - IL ROUTE 251 OVER N KINNIKINNICK CREEK SN 101-0035 (NB) & 0036 (SB)
14	CONCRETE REMOVAL DETAILS - SN 101-0035 (NB) & 0036 (SB)
15	CONCRETE REPLACEMENT DETAILS - SN 101-0035 (NB) & 0036 (SB)
16	PREFORMED JOINT STRIP SEAL DETAILS - SN 101-0035 (NB) & 0036 (SB)
17	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS - SN 101-0035 (NB) & 0036 (SB)
18	RAIL POST AND ANCHOR DEVICE DETAILS - SN 101-0035 (NB) & 0036 (SB)
19	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION - SN 101-0035 (NB) & 0036 (SB)
20	INFORMATIONAL WARNING SIGN (FOR NARROW TRAVEL LANES) (DIST STD 39.2)
	TRAFFIC CONTROL & PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (DIST STD 94.2)
21 - 23	TYPICAL PAVEMENT MARKINGS (DIST STD 41.1)
24	PAINTING DETAILS (DIST STD 44.1)

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

STANDARD NO.

000001-06

SHEET NO.

DESCRIPTION

INDEX OF SHEETS

001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
642001-02	SHOULDER RUMBLE STRIPS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE
701422-04	LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701423-05	LANE CLOSURE, MULTILANE, WITH BARRIER, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS $_{\rm 2}$ 45 MPI
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
720011-01	METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A AND B METAL POSTS (FOR SIGNS & MARKERS)
780001-03	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

GENERAL NOTES

ALL BORROWWASTE/USE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPILING OUTSIDE THE

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

	PAVEMENT	SHOULDER
MIXTURE USES(S):	SURFACE	SURFACE
PG:	PG 64-22	PG-58-22
DESIGN AIR VOIDS	4.0% @ N70	3.0% AT N50
MIXTURE COMPOSITION (GRADATION MIXTURE)	IL 9.5 OR 12.5	IL 9.5 OR 12.5
FRICTION AGGREGATE	MIX D	MIX C
20 YEAR ESAL		NA
MIX UNIT WEIGHT	112 LBS/SY/IN	112 LB/SY/IN

THE AREA TO BE PRIMED SHALL BE LIMITED TO THAT WHICH CAN BE COVERED WITH HMA ON THE NEXT DAYS PRODUCTIVITY, BUT NO MORE THAN FIVE DAYS IN ADVANCE OF THE PLACEMENT OF THE HMA, UNLESS APPROVED BY THE

INSTALL RUMBLE STRIPS IN ALL SHOULDERS IN ACCORDANCE WITH STATE STANDARD 642001. RUMBLE STRIPS SHALL BE PLACED ON SHOULDERS ON BOTH SIDES OF THE PAVEMENT.

BITUMINOUS AND AGGREGATE PRIME COAT SHALL BE PLACED IN ACCORDANCE WITH SECTION 406 OF THE STANDARD SPECIFICATIONS. THE COST OF THE PRIME COATS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER TON FOR HOT-MIX ASPHALT SURFACE COURSE OF THE TYPE SPECIFIED.

REFLECTOR MARKERS TYPE B SHALL BE INSTALLED ON THE TOP OF BRIDGE PARAPET WALLS. THE MARKERS SHALL BE ACCORDING TO STANDARD 635011 AND THE COLOR AND SPACING ACCORDING TO STANDARD 635006, EXCEPT THE MINIMUM IS 2 PER SIDE.

CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE YOUR RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.

TEMPORARY IMPACT ATTENUATORS WILL BE MEASURED AS EACH FOR EACH ATTENUATOR SUPPLIED ON THE JOB AS SPECIFIED IN THE PLANS, AND SHALL INCLUDE THE COST OF RENTING/OWNING THE ATTENUATOR FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, TEMPORARY OF THE TYPE SPECIFIED.

RELOCATE TEMPORARY IMPACT ATTENUATORS WILL BE PAID FOR AS EACH AND WILL BE PAID FOR EACH TIME THE ATTENUATOR IS REQUIRED BY STAGING TO BE WILL BE PAID FOR EACH TIME THE ATTENDATION IS REQUIRED BY TAKING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE. PER EACH FOR IMPACT ATTENUATORS, RELOCATE OF THE TYPE

THIS WORK SHALL BE DONE IN ACCORDANCE WITH SECTION 704 OF THE STANDARD SPECIFICATIONS. TEMPORARY CONCRETE BARRIER WILL BE MEASURED IN FEET ALONG THE CENTERLINE OF THE BARRIER AND SHALL INCLUDE THE COST OF RENTING/OWNING THE BARRIER FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY IN ACCORDANCE WITH SECTION 704 OF THE STANDARD SPECIFICATION. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR TEMPORARY CONCRETE BARRIER.

RELOCATE TEMPORARY CONCRETE BARRIER WILL BE PAID FOR IN FEET ALONG THE CENTERLINE OF THE BARRIER, AND WILL BE PAID FOR EACH TIME THE BARRIER IS REQUIRED BY STAGING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR RELOCATE TEMPORARY CONCRETE BARRIER.

FILE NAME = D264H22-sht-index.dgm PLOT DATE =1/23/2012 OT SCALE=50.0000 '/ IN.



	DESIGNED	-	G.F.L./K.R.K.	REVISED -
	DRAWN	-	K.R.K.	REVISED -
	CHECKED	-	E.J.M.	REVISED -
4	DATE	-	DECEMBER 2011	REVISED -
_			con a service de constitue de c	manage continues de de consentidades de management de contraction de la contraction

-	INDEX OF SHEETS, LIST OF STATE STANDARDS AND	F.A.P. RTE.	SECTION	
	GENERAL NOTES - IL 251 AT N. KINNIKINNICK CREEK	738	(5B-1)M-1	W
				(
	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.		TILLINOIS	