

NOTES

Detail I - With Bar Splicer or Couplers: Connect one (1) 1'' x 7' 'x ''W_' steel ft to the top layer of couplers with $2 - \frac{5}{8}$ " ϕ bolts screwed to coupler at approximate Q of each barrier panel. Detail II - With Extended Reinforcement Bars: Connect one (1) 1" x 7" x "W" steel P to the concrete slab or concrete wearing surface with 2- $\frac{5}{8}$ " ϕ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \mathcal{Q} of each barrier panel. Cost of anchorage is included with Temporary Concrete Barrier.

The 1" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready



* Required only with Detail II

RIER FOR STAGE CONSTRUCTION & S.N. 101–0036 (SB)			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			738	(5B-1)M-1	WINNEBAGO	24	19
					CONTRACT	NO. 6	4H22
HEETS	STA.	TO STA.		ILLINOIS			