

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50						40603310
			WIDTH	SQYD	INCHES	TONS
Stage 1						
SB	287+60.00	290+25.00	4	117.8	2	13.2
SB	291+27.00	293+90.00	4	116.9	2	13.1
NB	287+60.00	290+25.00	4	117.8	2	13.2
NB	291+27.00	293+90.00	4	116.9	2	13.1
Stage 2						
SB	287+60.00	289+77.00	4	96.4	2	10.8
SB	291+77.00	293+90.00	4	94.7	2	10.6
NB	287+60.00	289+77.00	4	96.4	2	10.8
NB	291+77.00	293+90.00	4	94.7	2	10.6
TOTAL						95.4

HOT-MIX ASPHALT SURFACE REMOVAL, 2"					44000157
			WIDTH	SQ YD	
Stage 1					
SB	287+60.00	290+25.00	4	117.8	
SB	291+27.00	293+90.00	4	116.9	
NB	287+60.00	290+25.00	4	117.8	
NB	291+27.00	293+90.00	4	116.9	
Stage 2					
SB	287+60.00	289+77.00	4	96.4	
SB	291+77.00	293+90.00	4	94.7	
NB	287+60.00	289+77.00	4	96.4	
NB	291+77.00	293+90.00	4	94.7	
TOTAL					851.6

SHOULDER RUMBLE STRIPS, 16 INCH					64200116
					FOOT
Stage 1					
SB	287+60.00	290+25.00			265.0
SB	291+27.00	293+90.00			263.0
NB	287+60.00	290+25.00			265.0
NB	291+27.00	293+90.00			263.0
Stage 2					
SB	287+60.00	290+25.00			265.0
SB	291+27.00	293+90.00			263.0
NB	287+60.00	290+25.00			265.0
NB	291+27.00	293+90.00			263.0
TOTAL					2112.0

SHORT TERM PAVEMENT MARKING					70300100
					FOOT
SOUTHBOUND					
SKIP-DASH	276+50.00	293+40.00			139
YELLOW	287+60.00	293+90.00			208
WHITE	287+60.00	293+90.00			208
NORTHBOUND					
SKIP-DASH	288+10.00	303+30.00			125
SKIP-DASH	304+50.00	316+00.00			95
YELLOW	287+60.00	293+90.00			208
WHITE	287+60.00	293+90.00			208
WHITE	304+51.00	307+37.00			94
WHITE	304+51.00	307+46.00			97
TOTAL					1383.0

TEMPORARY CONCRETE BARRIER				70400100
				FOOT
STAGE 1				
288+63.44	291+93.50			325
289+57.53	292+85.82			325
TOTAL				650

RELOCATE TEMPORARY CONCRETE BARRIER				70400200
				FOOT
STAGE 2				
288+89.00	291+93.57			300
289+57.62	292+60.56			300
TOTAL				600

TEMPORARY PAVEMENT MARKING - LINE 4"						70300220
				FOOT	FOOT	
STAGE 1						
SOUTHBOUND						
	276+50.00	293+40.00				1690
	287+60.00	293+90.00		630		
NORTHBOUND						
	288+10.00	302+80.00				1470
	287+60.00	293+90.00		630		
	303+00.00	303+61.00				56
	303+00.00	303+46.00				46
	304+27.00	307+15.00				288
	304+27.00	304+27.00				29
	304+15.00	306+63.00		248		
	306+63.00	307+15.00				52
	307+00.00	316+60.00				960
STAGE 2						
SOUTHBOUND						
	276+50.00	293+40.00		1,690		
	287+60.00	293+90.00			630	
NORTHBOUND						
	288+10.00	303+28.00		1,518		
	287+60.00	293+90.00			630	
	304+27.00	304+27.00				12
	304+27.00	307+13.00				286
	304+27.00	306+65.00		238		
	306+65.00	307+13.00				48
	307+00.00	316+60.00				960
TOTAL					5,914	6,224
						12,138

WORK ZONE PAVEMENT MARKING REMOVAL						70301000
				FOOT	FOOT	SQ. FT.
STAGE 1						
SOUTHBOUND						
	276+50.00	293+40.00			1690	563.33
	287+60.00	293+90.00		630		210.00
NORTHBOUND						
	288+10.00	302+80.00			1470	490.00
	287+60.00	293+90.00		630		210.00
	303+00.00	303+61.00			56	18.67
	303+00.00	303+46.00			46	15.33
	303+61.00	303+61.00			27	9.00
	304+27.00	307+15.00			288	96.00
	304+27.00	304+27.00			29	9.67
	304+15.00	306+63.00		248		82.67
	306+63.00	307+15.00			52	17.33
	307+00.00	316+60.00			960	320.00
STAGE 2						
SOUTHBOUND						
	276+50.00	293+40.00		1,690		563.33
	287+60.00	293+90.00			630	210.00
NORTHBOUND						
	288+10.00	303+28.00		1,518		506.00
	287+60.00	293+90.00			630	210.00
	304+27.00	304+27.00				4.00
	304+27.00	307+13.00			286	95.33
	304+27.00	306+65.00		238		79.33
	306+65.00	307+13.00			48	16.00
	307+00.00	316+60.00			960	320.00
TOTAL					5,914	6,224
						4,046

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70						40603340
				SQYD	INCHES	TONS
SB NORTH APPROACH	289+77.00	290+27.00		177.0	1.75	17.3
SB SOUTH APPROACH	291+27.00	291+77.00		215.0	1.75	21.1
NB NORTH APPROACH	289+77.00	290+27.00		214.0	1.75	21.0
NB SOUTH APPROACH	291+27.00	291+77.00		178.0	1.75	17.4
TOTAL						784

GUARDRAIL MARKERS, TYPE A					78200410
				25' SPACING	TOTAL
SOUTHBOUND					
	287+70.00	290+25.00		/25	10
	288+65.00	290+25.00			6
NORTHBOUND					
	291+25.00	292+90.00			7
	291+25.00	293+80.00			10
TOTAL					23

HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"				44000156
				SQYD
SB NORTH APPROACH	289+77.00	290+27.00		177.0
SB SOUTH APPROACH	291+27.00	291+77.00		215.0
NB NORTH APPROACH	289+77.00	290+27.00		214.0
NB SOUTH APPROACH	291+27.00	291+77.00		178
TOTAL				784.0

BARRIER WALL MARKERS, TYPE B					78200520
				25' SPACING	EACH
SOUTHBOUND					
	290+25.00	291+25.00		/25	4
	290+25.00	291+25.00			4
NORTHBOUND					
	290+25.00	291+25.00			4
	290+25.00	291+25.00			4
TOTAL					12

THERMOPLASTIC PAVEMENT MARKING - LINE 4"					78000200
					FOOT
SOUTHBOUND					
YELLOW	287+60.00	293+90.00			630
WHITE	287+60.00	293+90.00			630
NORTHBOUND					
YELLOW	287+60.00	293+90.00			630
WHITE	287+60.00	293+90.00			630
TOTAL					2,520

THERMOPLASTIC PAVEMENT MARKING - LINE 6"					78000400
					FOOT
SOUTHBOUND					
SKIP-DASH	276+50.00	293+40.00			423
NORTHBOUND					
SKIP-DASH	288+10.00	303+30.00			380
SKIP-DASH	304+50.00	316+00.00			288
TOTAL					1091.0

THERMOPLASTIC PAVEMENT MARKING - LINE 8"					78000500
					FOOT
NORTHBOUND					
WHITE	304+51.00	307+37.00			286
WHITE	304+51.00	307+46.00			295
TOTAL					581

REPLACEMENT REFLECTOR				78100300
SOUTHBOUND				
SKIP-DASH	277+70.00	293+40.00		20
NORTHBOUND				
SKIP-DASH	288+10.00	303+30.00		19
SKIP-DASH	304+50.00	316+00.00		14
TOTAL				53

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)					78100105
					EACH
Stage 1					
SB	290+25.00	291+27.00			1
NB	290+25.00	291+27.00			1
TOTAL					2

PAVEMENT MARKING REMOVAL					78300100
					SQ. FT.
SOUTHBOUND					
SKIP-DASH	276+50.00	293+40.00		423	211.25
YELLOW	287+60.00	293+90.00		630	207.90
WHITE	287+60.00	293+90.00		630	207.90
NORTHBOUND					
SKIP-DASH	288+10.00	303+30.00		380	190.00
SKIP-DASH	304+50.00	316+00.00		288	143.75
YELLOW	287+60.00	293+90.00		630	207.90
WHITE	287+60.00	293+90.00		630	207.90
WHITE	304+51.00	307+37.00		286	191.62
WHITE	304+51.00	307+46.00		295	197.65
TOTAL					1765.9

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL					78300200
SB	290+25.00	291+27.00			1
NB	290+25.00	291+27.00			1
Total on Bridge					2

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3					Z0030250
					EACH
STAGE 1					
288+63.00	SB				1
2					