

SUMMARY OF QUANTITIES

CONSTRUCTION CODE
90% FED 10% STATE
0014
<i>URBAN</i>

*SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	49,055
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16,351
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4,525.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,525.0
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	250
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
*72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1
*72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	18,091
*78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1,120
*78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	234

SUMMARY OF QUANTITIES

CONSTRUCTION CODE
90% FED 10% STATE
0014
<i>URBAN</i>

*SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	29
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	60
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	829
78200410	GUARDRAIL MARKERS, TYPE A	EACH	7
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5,626
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	58
X0322392	BEVELED PIPE AND GUARD	EACH	2
*X0325712	RELOCATE EXISTING ELECTRICAL SYSTEM	L SUM	1
X5810100	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SQ YD	9,692
*X6330075	RELOCATE TRAFFIC BARRIER TERMINAL, (TEMPORARY)	EACH	2
X6380205	TEMPORARY MODULAR GLARE SCREEN	FOOT	450
*X7050169	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)	EACH	1
*X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1