

PAVEMENT MARKING SCHEDULE														
LOCATION		70300220	70301000	78005110	78005130	78005140	78100100	78100105	78100200	78300100	78300200			
		TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	COLOR	NOTE	LOCATION
BEGIN STATION	END STATION	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH	EACH	SQ FT	EACH			
<b>STAGE 2</b>														
2361+00.00	2441+12.50	8013	2671									Yellow	Solid edge line	NB lane on LT
2398+00.00	2443+62.50	4563	1521									White	Solid edge line	NB lane on RT
2401+00.00	2447+00.00	4615	1538									Yellow	Solid edge line	SB lane on LT thru crossover
2403+13.00	2473+50.00	7068	2356									White	Solid edge line	SB lane on RT thru crossover
2398+00.00	2443+62.50			4563								White		NB outside edge
2401+00.00	2447+00.00			4600								Yellow		NB inside edge
2405+35.00	2448+62.50			4328								White		SB outside edge
2401+00.00	2447+00.00			4600								Yellow		SB inside edge
2361+00.00	2371+00.00				250							White		NB center skip
2419+11.00	2430+70.00				290							White		NB center skip
2418+30.00	2431+55.00				330							White		SB center skip
2463+50.00	2473+50.00				250							White		SB center skip
2377+06.00	2378+23.00					117						White		NB gore edge
16+43.50	17+60.20					117						White		Baster Ramp gore edge
2361+00.00	2371+00.00						13							NB lanes
2430+44.00	2430+69.00						1							NB lanes
2418+30.00	2419+60.00						2							SB lanes
2463+50.00	2473+50.00						13							SB lanes
2418+81.00	2430+44.00							30						NB Bridge
2419+60.00	2431+30.00							30						SB Bridge
2398+00.00	2419+11.00								704					NB edge RT
2430+01.00	2443+62.50								454					NB edge RT
2404+00.00	2419+11.00								504					NB edge LT
2430+01.00	2443+00.00								433					NB edge LT
2401+00.00	2405+00.00								133					SB edge LT
2442+00.00	2447+00.00								167					SB edge LT
2418+30.00	2431+55.00									17				SB bridge & approach
2361+00.00	2380+00.00							48						NB LT
2380+00.00	2410+00.00							75						NB LT
2398+00.00	2410+00.00							30						NB RT
2403+13.00	2409+38.20							31						SB RT
2409+38.20	2410+00.00							2						SB RT
2410+00.00	2415+97.70							15						NB RT
2410+00.00	2418+81.00							22						SB RT
2430+44.00	2440+00.00							24						NB RT
2433+37.20	2438+61.90							13						SB RT
2439+00.00	2440+00.00							5						SB LT
2438+61.90	2440+00.00							7						SB RT
2440+00.00	2443+62.50							9						NB RT
2440+00.00	2447+00.00							35						SB LT
2440+00.00	2447+00.00							35						SB RT
2447+00.00	2470+00.00							58						SB RT
2470+00.00	2473+50.00							9						SB RT
<b>SUBTOTAL</b>		<b>24259</b>	<b>8086</b>	<b>18091</b>	<b>1120</b>	<b>234</b>	<b>29</b>	<b>60</b>	<b>418</b>	<b>2395</b>	<b>17</b>			
<b>TOTALS</b>		<b>49055</b>	<b>16351</b>	<b>18091</b>	<b>1120</b>	<b>234</b>	<b>29</b>	<b>60</b>	<b>829</b>	<b>5626</b>	<b>58</b>			

FILE NAME =  
 USER NAME = brenn00248  
 DESIGNED - BJB  
 DRAWN - BJB  
 CHECKED - JMH  
 DATE - 2/9/12  
 PLOT SCALE = 1/8" = 1' / in.  
 PLOT DATE = 02/18/2012

DESIGNED - BJB  
 DRAWN - BJB  
 CHECKED - JMH  
 DATE - 2/9/12  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**  
**I-39 OVER KISHWAUKEE RIVER**  
 SCALE: SHEET 3 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(201-1B)M-3	WINNEBAGO	38	10
CONTRACT NO. 64H72				
ILLINOIS FED. AID PROJECT				