

SCHEDULE OF QUANTITIES

MOBILIZATION

LOCATION	LSUM
JOBSITE	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
East & West Jobsite Approaches	2
TOTAL	2

EPOXY MRKG.-LINE, 4"

LOCATION	FOOT
Jobsite - SN.029-0025	1482
TOTAL	1482

IMPACT ATTENUATORS, TEMP. NRD, TL 3

LOCATION	EACH
Jobsite - SN.029-0025	2
TOTAL	2

T.C.& P STANDARD 701321

LOCATION	EACH
JOBSITE	1
TOTAL	1

PVMT. MRKG. TAPE, TYPE III, 4"

LOCATION	FOOT
Jobsite Traffic Staging Lanes	3628
TOTAL	3628

PVMT. MRKG. REMOVAL

LOCATION	FOOT
Jobsite - SN.029-0025	1482
TOTAL	1482

IMPACT ATTENUATORS, RELOCATE NRD, TL 3

LOCATION	EACH
Jobsite - SN.029-0025	2
TOTAL	2

T.C.& P STANDARD 701201

LOCATION	LSUM
JOBSITE	1
TOTAL	1

WORKZONE PVMT. MRKG. REMOVAL

LOCATION	SQFT
Jobsite Traffic Staging Lanes	1210
TOTAL	1210

STRUCTURAL REPAIR OF CONCRETE (<= 5")

LOCATION	SQFT
Pier 1 Cap (South End)	12
TOTAL	12

TEMP. BR. TRAFFIC SIGNALS

LOCATION	EACH
Traffic Staging Approaches	1
TOTAL	1

TEMP. CONC. BARRIER

LOCATION	FOOT
Jobsite - SN.029-0025	687.5
TOTAL	687.5

THERMAL SPRAYING (METALIZING) BR. CONC. SFC.

LOCATION	SQFT
Bent Piling Surfaces	270
TOTAL	270

TEMP. RUMBLE STRIP

LOCATION	EACH
Jobsite Approaches	12
TOTAL	12

RELOCATE TEMP. CONC. BARRIER

LOCATION	FOOT
Jobsite - SN.029-0025	687.5
TOTAL	687.5

DECK SLAB REPAIR (PARTIAL)

LOCATION	SQYD
Jobsite	25
TOTAL	25

S:\GEN. DRFTY. STDRPLNS. S0400141_68A5B.SN.029-0025.dwg

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SN.029-0025 IL.95 OVER SPOON RIVER	F.A.P. RTE. 687	SECTION (123B)	COUNTY FULTON	TOTAL SHEETS 14	SHEET NO. 4
#FILE#	PLOT SCALE = *SCALE*	CHECKED -	REVISED -		SCALE: _____	CONTRACT MAINT. BRIDGE REPAIRS		CONTRACT: 68A5B		
	PLOT DATE = *DATE*	DATE -	REVISED -		SHEET NO. ____ OF ____ SHEETS	ILLINOIS FED. AID PROJECT				