

AGGREGATE SHOULDERS, TYPE B

TYP. SEC. #	LOCATION	QUANTITY (TON)
	F. A. P. 514 ( IL 94)	
( 1-2)	STA. 5+15.16 TO STA. 6+28.89	8.64
	( BRIDGE OMISSION ) S. N. 034-0060	
	STA. 6+28.89 TO STA. 8+44.89	
( 3-21)	STA. 8+44.89 TO STA. 219+00.00	1,598.63
	SUBTOTAL	1,607.26
	[ SUBTRACT ]	
	SIDE ROADS & ENTRANCES	27.17
	PROJECT TOTAL	1,580

STRIP REFLECTIVE CRACK CONTROL TREATMENT

TYP. SEC. #	LOCATION	QUANTITY ( FOOT )
	F. A. P. 514 ( IL 94)	
	( BRIDGE OMISSION ) S. N. 034-0060	
	STA. 6+28.89 TO STA. 8+44.89	
( 3-18)	STA. 8+44.89 TO 213+35.00	42,110.22
	PROJECT TOTAL	42,111

GUARDRAIL MARKER, TYPE B

TYP. SEC. #	LOCATION	QUANTITY ( EACH )
	F. A. P. 514 ( IL 94)	
( 17)	STA. 135+18.00 TO STA. 138+67.00 RT	5
( 17)	STA. 136+56.00 TO STA. 139+72.00 LT	4
	PROJECT TOTAL	9

AGGREGATE SURFACE COURSE, TYPE B

LOCATION	QUANTITY ( TON )
F. A. P. 514 ( IL 94)	
Quantity for HMA PE's and CE's	10.92
PROJECT TOTAL	11

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

TYP. SEC. #	LOCATION	QUANTITY ( FOOT )
	F. A. P. 514 ( IL 94)	
	NEW GUARDRAIL	
( 17)	STA. 135+28.00 TO STA. 138+57.00 RT	329.00
( 17)	STA. 136+66.00 TO STA. 139+62.00 LT	296.00
	PROJECT TOTAL	625

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL ( TANGENT )

TYP. SEC. #	LOCATION	QUANTITY ( EACH )
	F. A. P. 514 ( IL 94)	
( 17)	STA. 135+28.00 TO STA. 135+78.00 RT	1
( 17)	STA. 136+66.00 TO STA. 137+16.00 LT	1
( 17)	STA. 138+07.00 TO STA. 138+57.00 RT	1
( 17)	STA. 139+12.00 TO STA. 139+62.00 LT	1
	PROJECT TOTAL	4

TERMINAL MARKER-DIRECT APPLIED

TYP. SEC. #	LOCATION	QUANTITY ( EACH )
	F. A. P. 733 ( IL 61/94)	
( 17)	STA. 135+28.00 RT	1
( 17)	STA. 136+65.00 LT	1
( 17)	STA. 138+57.00 RT	1
( 17)	STA. 139+62.00 LT	1
	PROJECT TOTAL	4